

# Development of High Pressure Hydrogen Storage Tank for Storage and Gaseous Truck Delivery



Don Baldwin, Principal Investigator

Norm Newhouse, Presenter

Hexagon Lincoln

May 15, 2013

Project ID#

PD021

# OVERVIEW

## Timeline

- Phase I July 08 – June 09
  - 100% Complete
- Phase II June 09 – April 13

## Budget

- Total project funding (Phase I & II)
  - DOE share \$3M
  - Contractor share \$2.73M
- Funding received in FY12 - \$489K

## Barriers

- Barriers addressed
  - E. Gaseous Hydrogen Storage and Tube Trailer Delivery Costs
  - I. Other Fueling Site/Terminal Operations

## Partners

- Discussions with ABS on vessel qualification
- Discussions with US DOT

## RELEVANCE

- **Relevance:** to reduce the cost of a near-term means of transporting gaseous H<sub>2</sub> from the production or city gate site to the station.
- Design and develop the most effective bulk hauling and storage solution for hydrogen in terms of cost, safety, weight, and volumetric efficiency. This will be done by developing and manufacturing a tank and corresponding ISO frame that can be used for the storage of hydrogen in a stationary or hauling application. **Complete 4Q 2009.**
- Based on current knowledge of tube trailer design, carry out preliminary design and qualify a 3600 psi tank and ISO frame that will hold 510000 in<sup>3</sup> (~8500L) water volume. **Complete 4Q 2009.**
- Complete trade studies needed to increase vessel capacity by increasing pressure to 5000 psi (ultimately exceeds the DOE's FY01 capacity target by >15%). **Complete 1Q 2011.**
- Complete the enhancement of the 250 bar system with respect to capacity (> 700 kg/liter) and safety (fire protection). **Complete 4Q 2012.**

# OBJECTIVES-TECHNICAL TARGETS 2010/2015\*

Hydrogen delivery targets	ISO container with four 3600 psi tanks (FY 2009 Work Scope)
<p>\$500/kg of hydrogen stored by FY2010, \$300/kg by FY2015</p>	<p>The TITAN Module, with four tanks installed, met the \$500 per kg hydrogen objective in 2010. However, since 2010 increases in market prices for materials of construction (specifically carbon fiber and specialty forgings) have forced us to increase our current pricing to about \$800/kg (1Q 2013). [We have strong domestic and international sales of our high-capacity modules and trailers at this price level for CNG.]</p>
<p>Volumetric capacity 0.03 kg/liter by FY2010, &gt;0.035 kg/liter by FY 2015</p>	<p>The baseline tank has a capacity of 150 kg hydrogen in a volume of ~8500 liters, achieving a performance of ~0.018 kg/liter.</p>
<p>Tube trailer delivery capacity 700 kg by FY2010 and 1,140 kg by FY2017</p>	<p>The current ISO assembly, with four tanks installed, will contain approximately 616 kg of hydrogen. At 90% hauling efficiency, delivery of 555 kg of hydrogen</p>

\* Based on the Fuel Cell Technologies Office 2007 MYRD&D




# OBJECTIVES-TECHNICAL TARGETS 2015/2020

Hydrogen delivery targets	ISO container with four 3600 psi tanks (FY 2009 Work Scope)
\$730/kg of hydrogen delivered by FY2015, \$575/kg by FY2015	The TITAN Module, with four tanks installed, met the \$500 per kg hydrogen objective in 2010. However, since 2010 increases in market prices for materials of construction (specifically carbon fiber and specialty forgings) have forced us to increase our current pricing to about \$800/kg (1Q 2013). [We have strong domestic and international sales of our high-capacity modules and trailers at this price level for CNG.]
Delivery Pressure 400 bar by FY2015, 520 bar by FY2020	The current delivery pressure is 250 bar. Design and trade studies have been performed which indicate that a delivery pressure of 350 bar is optimal for TITAN modules/trailers. Higher pressures are achievable but would require extensive redesign and retooling of the manufacturing infrastructure. Any further validation and homologation activity must be preceded by industry consensus on delivery pressure and better definition of the business opportunity
Tube trailer delivery capacity 700 kg by FY2015 and 940 kg by FY2020	The Titan module system, (four large tanks) contains approximately 616 kg of hydrogen. At 90% hauling efficiency, delivery of 555 kg of hydrogen The Titan 5 ( 5 large tank trailer) contains approximately 726 kg of hydrogen. At 90% hauling efficiency, delivery of approximately 653 kg of hydrogen The Titan 5 Magnum, (5 large tanks and 9 small tanks) contains approximately 800 kg of hydrogen. At 90% hauling efficiency, delivery of approximately 720 kg of hydrogen.



# APPROACH/MILESTONES



# TECHNICAL ACCOMPLISHMENTS/PROGRESS/RESULTS



DOE Hydrogen Program

- ▶ **Completed the design, manufacture and assembly of ISO format container (standard dimensions) capable of storing ~616 kg H<sub>2</sub> @ 3600 psi.**
  - **Successful completion of all qualification tests for a 3600 pressure vessel per ABS Document No. ABSHOU557163**
  - **Completed Testing of Container per CSC 49 CFR Part 451**
  - **DOT Special Permit 14951 issued 22 February 2012**







## TECHNICAL ACCOMPLISHMENTS/PROGRESS/RESULTS

- Completed the design, manufacture and assembly of integrated trailer system capable of storing ~800 kg H<sub>2</sub> @ 3600 psi.
  - Maximum width and height allowed on Interstate Highway System
  - Gross Vehicle Weight within limits for Interstate up to 350 bar



# TECHNICAL ACCOMPLISHMENTS/PROGRESS/RESULTS



DOE Hydrogen Program

## HEXAGON LINCOLN TITAN™ V Magnum Trailer System

### Compressed Hydrogen Gas

#### Capacity


- 250 bar – 800 kg (720 kg delivered)
- 350 bar – 1050 kg (907 kg delivered)
- 540 bar – 1500 kg (1350 kg delivered)

#### Gross Vehicle Weight (with prime mover)

- 250 bar – 31 000 kg
- 350 bar – 34 200 kg
- 540 bar – 45 700 kg

#### Purchase Cost

- 250 bar – \$595,000 (\$744/kg)
- 350 bar – \$745,000 (\$710/kg)
- 540 bar – \$1,295,000 (\$863/kg)




24.02.05-0001

24.02.05-0001

### Compressed Natural Gas

- Capacity (250 bar at 15 C) – 9649 kg
- GVW (With prime mover) – 39 830 kg
- Purchase Cost (+/- 5%) - \$595,000




# TECHNICAL ACCOMPLISHMENTS/PROGRESS/RESULTS



DOE Hydrogen Program

## OPERATIONAL PARAMETERS FOR BULK HAULING EQUIPMENT

- More Hydrogen Capacity and Lower GVW Reduces Operating Expenses
- 350 bar TITAN™ and TITAN V Magnum™ Would be a Logical Next Step
  - 2.25 SR Design Fits ISO Frame and Trailer Widths
  - .018 to .024 kg H<sub>2</sub> per Liter
  - 616 to 816 kg H<sub>2</sub> Capacity for TITAN™, 801 to 1051 kg H<sub>2</sub> Capacity for TITAN V Magnum™
  - 5% reduction in \$ per kg H<sub>2</sub> [capital expenditure for rolling stock only]
  - Practical Limit in Industry is 350 bar
    - Higher pressures exacerbates thick-wall effects and reduced strength translation
    - Availability of Plumbing Hardware
    - Availability of H<sub>2</sub> Compressors
- Need Definition of Market Size and Operating Parameters [i.e.; 350 bar vs 540 bar] before a Business Case Can be Made for Investment in Qualification at a Higher Pressure





# TECHNICAL ACCOMPLISHMENTS/PROGRESS/RESULTS




DOE Hydrogen Program

## OPERATIONAL PARAMETERS FOR BULK HAULING EQUIPMENT



# TECHNICAL ACCOMPLISHMENTS/PROGRESS/RESULTS



- Completed the build of laboratory area that enables Hexagon Lincoln to begin looking at the effect of hydrogen on polymers that are and could potentially be used as liner materials
  - Capable of using 100% hydrogen up to 700 bar
  - Automated pressure cycling
  - Variable depressurization rates
    - Minimum - 30 psi/minute
    - Maximum - 160,000 psi/minute

## COLLABORATIONS

- American Bureau of Shipping on qualification of existing and potential changes to composition of current pressure vessels.
- Lincoln Composites has received Special Permit from the U.S. DOT authorizing the manufacture, making, sale and use of the Titan bulk hauling 4 cylinder module in February 2012.

## SUMMARY

- Hydrogen delivery and storage are key to the roll out of PEMFC technology
- Low cost, near-term delivery pathways such as tube trailer transport will enable early adoption of these technologies
- Developing a bulk storage unit that can be transported on an ISO frame is a critical part of this strategy

Technical Targets*	
DOE Goals	Estimated Results
\$500/kg of hydrogen stored by FY2010, \$300/kg by FY2015	3600 psi - \$500 per kg of H <sub>2</sub>
Volumetric capacity 0.03 kg/liter by FY2010, >0.035 kg/liter by FY 2015	Current 3600 psi tank – 0.018 kg/liter
Tube trailer delivery capacity 700 kg by FY2010 and 1,100 kg by FY2017	3600 psi (4-tube ISO container) - contains 616 kg of hydrogen, 555 kg deliverable at 90% efficiency.
Tube trailer delivery capacity 700 kg by FY2015 and 940 kg by FY2020 (DRAFT)	3600 psi (4-tube ISO container) - contains 616 kg of hydrogen, 555 kg deliverable at 90% efficiency. 3600 psi (5-tube trailer) – contains 726 kg of hydrogen, 653 kg deliverable at 90% efficiency. 3600 psi (5-tube trailer with additional 9 tanks) – contains 800kg of hydrogen, 720 kg deliverable at 90% efficiency.
Tube trailer operating pressure goal is <10,000 psi by FY2012	Current module configuration is 3600 psi

\* Based on the Fuel Cell Technologies Office 2007 MYRD&D