

## VI.11 Extended Durability Testing of an External Fuel Processor for SOFC\*

Mark Perna

Rolls-Royce Fuel Cell Systems (U.S.) Inc.  
6065 Strip Avenue NW  
North Canton, OH 44720  
Phone: (330) 491-4830; Fax: (330) 491-4808  
E-mail: Mark.Perna@US.RRFCS.com

DOE Technology Development Manager:

Dimitrios Papageorgopoulos

Phone: (202) 586-5463; Fax: (202) 586-2373  
E-mail: Dimitrios.Papageorgopoulos@ee.doe.gov

DOE Project Officer: Jesse Adams

Phone: (303) 275-4954; Fax: (303) 275-4753  
E-mail: Jesse.Adams@go.doe.gov

Contract Number: DE-FG36-08GO88113

Project Start Date: January 9, 2009

Project End Date: October 31, 2010

\*Congressionally directed project

### Objectives

The main goal of this project is to perform extended durability testing of the External Fuel Processor for the Rolls-Royce Fuel Cell Systems (RRFCS) 1-MWe solid oxide fuel cell (SOFC) power plant concept. The specific objectives are to:

- Conduct long-term tests in relevant environment of the External Fuel Processor.
- Determine long-term performance of critical components including catalysts, sorbents, heat exchangers, control valves.
- Evaluate the impact of ambient temperatures (hot and cold environments) on performance and component reliability.
- Determine system response and performance of process controls for transient operation.
- Identify any failure mechanisms.

### Technical Barriers

This project addresses the following technical barriers from the Fuel Cells Section of the Hydrogen, Fuel Cells and Infrastructure Technologies (HFCIT) Program Multi-Year Research, Development and Demonstration (RD&D) Plan:

- (A) Durability
- (C) Performance

### (G) Start-up and Shut-down Time and Energy/Transient Operation

These barriers will be addressed as they relate to the External Fuel Processor subsystem in the RRFCS 1-MWe SOFC power plant concept. The External Fuel Processor subsystem uses pipeline natural gas and air to generate all gas streams required by the fuel cell power plant for start-up, shut-down, low-load and normal operation. Thus it eliminates the need for on-site bottled gases.

### Technical Targets

This project addresses Milestone 59 in the Fuel Cells section of the HFCIT Multi-Year RD&D Plan. Milestone 59 is to “evaluate fuel processing subsystem performance for distributed generation against system targets for 2011.” These targets will be addressed as they relate to durability, performance (gas quality - sulphur in product stream), and transient response.

Characteristic	Units	2005 Status	DOE 2011 Targets	RRFCS 2011 Targets
Cold start-up time to rated power @ -20°C ambient	minutes	<90	<30	<30 from standby
Transient response time (for 10% to 90% power)	minutes	<5	1	1
Durability	hours	20,000	40,000	8,000
Survivability (min and max ambient temperature)	°C °C	-25 +40	-35 +40	-35 <sup>a</sup> +40 <sup>a</sup>
Sulfur content in product stream	ppbv (dry)	<10	<4	<80 ppb

<sup>a</sup> as limited by ambient conditions



### Approach

The approach for this project focuses on using full-scale components from the External Fuel Processor. It includes the following:

Conduct demonstration tests in relevant environments for:

- Synthesis-gas subsystem for multiple startups and 1,200 hours of operation in a heated indoor test enclosure.

- Start-gas subsystem for multiple startups and 200 hours of steady-state operation in an outdoor test facility (hot and cold environments).
- Desulfurizer subsystem for 8,000 hours in an outdoor test facility (hot and cold environments).

Perform post-test inspections on:

- Subsystem components (catalysts, sorbents, piping, reactors, insulation, valves, heaters, heat exchangers, N<sub>2</sub>-membrane, etc.).
- Deposits, signs of wear, damage, corrosion, erosion, and any failed components. Perform functional checks where possible.

### Accomplishments

The project was initiated in January 2009. By the end of the second quarter of 2009 the following tasks were completed:

- Draft Hydrogen Safety Plan issued for comments.
- Completed mechanical installation of synthesis-gas subsystem in test enclosure.
- Confirmed operation of enclosure safety system.
- Electrical wiring for control system completed.
- Control software written and debugged.
- Specifications for outdoor test facility issued.

### Future Directions

#### 2009

- Complete synthesis-gas subsystem durability test (Fiscal Year 2009 Q3).
- Complete post-test inspections (FY 2009 Q4).
- Complete installation and commissioning of start-gas and desulfurizer subsystems (FY 2009 Q3).
- Being durability testing of start-gas and desulfurizer subsystems (FY 2009 Q4).

#### 2010

- Complete durability testing of start-gas and desulfurizer subsystems (FY 2010 Q3).
- Complete inspections of start-gas and desulfurizer subsystems (FY 2010 Q4).
- Issue final report for project (FY 2010 Q4).

### FY 2009 Publications/Presentations

1. Presentation at 2009 Hydrogen Program Annual Merit Review Meeting, M. Perna.
2. Presentation at 2009 Project Kickoff Meeting, M. Perna.