



DOE Hydrogen Program Technology Validation Sub-Program

Sig Gronich John Garbak Office of Hydrogen, Fuel Cells, & Infrastructure Technologies May 25, 2005

Project #: TV1



Objectives



Validate integrated hydrogen and fuel cell technologies for transportation, infrastructure, and electric generation in a systems context under real-world operating conditions.

- By 2005, \$3.60/gge and 8¢/kWh.
- By 2008, 20,000 hour fuel-cell durability (stationary), 32% efficiency, \$1,500/kW
- By 2009, 250+ mile range, 2000 hour fuel-cell durability (vehicle), \$3.00/gge hydrogen (untaxed)
- By 2011, biomass/wind or geothermal electrolyzerto-hydrogen system to produce hydrogen for \$2.85/gge at the plant gate







Task 1 Vehicle Field Evaluations

- Task 2 Hydrogen Infrastructure Power Parks
- Task 3 Natural Gas-to-Hydrogen Refueling Stations
- Task 4 Co-Production of Hydrogen and Electricity
- Task 5 Renewable Hydrogen Production Systems
- Task 6 Technical Analyses



Budget



Task		DC	Cost Shares	
		EW&D	Interior	
1	Fleet & Infrastructure	\$6,359,761	\$16,713,129	\$21,781,890
2	Power Parks	\$720,000		\$720,000
3	Natural Gas to H2 Refueling Stations	\$1,178,355		\$878,355
4	Energy Station	\$350,000		\$350,000
5	Renewable	\$0		\$0
6	Analyses	\$250,000	\$351,000	\$0
1&4	Earmarks	\$5,059,000		\$5,059,000



Congressionally Directed Projects




California	\$4,960,000	Tasks	Develop, build, and test hydrogen infrastructure
Infrastructure	(2005)	1 & 4	
Locomotive fuel cell	\$300,000	Task	Develop, build & test
	(2005)	1	underground H2 mine loader
Bus Evaluation	\$99,000	Task	Analyze zero emissions bus –
	(2005)	1	Santa Clara, CA
Univ. of Alabama Birmingham	\$963,372 (2003)	Task 1	Test stationary and vehicle hydrogen systems
Hawaii Energy Center	\$992,000 (2005) \$2,982,000 (2004)	Task 2	Develop fuel cell test center
Hawaii Power	\$490,539	Task	Build and test power parks
Park	(2004)	2	



Congressionally Directed Projects Continued




NEXT Energy	\$793,096 (2003)	Task 2	Build and test refueling station
Chattanooga	\$2,485,250 (2004)	Task 4	Develop, build and test solid oxide fuel cell coproduction system
Washoe County	\$1,962,155 (2004) \$992,000 (2005)	Task 5	Develop, build & test geothermal/ electrolyzer refueling station
UNLV	\$963,372 (2003)	Task 5	Build and test photovoltaic refueling station
Florida Hydrogen Partnership	\$1,962,155 (2004)		Hydrogen research and development





FY 2005: Requested DOE Hydrogen Program Budget, by Category (\$227M)





Task 1 – Vehicle Field Evaluation "Learning Demonstration"



Description

- Support CaFCP vehicle and bus demonstration
- Support Controlled Fleet demonstrations (collect vehicle operating experience from different geographic regions)
- Design, build and test hydrogen locomotive and front-end loader vehicles



CaFCP Bus Demonstration





Hickam Air Force Base



Santa Clara Valley Transportation Authority

California Fuel Cell Bus Demonstration Sites Pacific Bakersfield Mayle



SunLine Transit Agency



Alameda Contra-Costa Transit Agency

- Completed evaluation of ThunderPower bus at SunLine
- Data collection in progress at Santa Clara VTA and Hickam AFB
- Infrastructure in place for the Alameda Contra-Costa Transit Agency



Technology Validation Strategy



 Conduct learning demonstrations of hydrogen infrastructure in parallel with hydrogen fuel cell-powered vehicles to enable and assess technology readiness for a 2015 commercialization decision.

Major Objectives

- Obtain detailed component data under real-world conditions (climatic, geographic etc.) to re-focus the Department's hydrogen and fuel cell component and materials research
- Validate the technology against time-phased performancebased targets



Learning Demonstration Description and Performance Targets




- FY 2004 2009 Project Period
- Government/industry cost shared co-operative agreement
- \$190M Government share subject to the appropriations process
- 2 Generations of vehicles
- Cold climates to be included by 2nd generation
- Renewable feedstock for H2 generation included
- Codes, Standards and Education integral to the success of the project
- Stationary facilities that co-produce electricity and hydrogen are included

Key Targets

Performance Measure	2009*	2015**		
Fuel Cell Stack Durability	2000 hours	5000 hours		
Vehicle Range	250+ miles	300+ miles		
Hydrogen Cost at Station	\$3.00/gge	\$1.50/gge		
* To verify progress toward 2015 targets ** Subsequent projects to validate 2015 target				



Cooperative Agreements Have Begun



UTC Fuel Cells

Awarded 4 cooperative agreements 1 project in negotiation

(1) Fuel cells supplied by Ballard



Data Collection & Analysis Process



Developed Secure Data Center and composite data products


Raw Data, Reports


- @ NREL: Strictly Controlled Access
- Detailed Analyses,
 Data Products, Internal
 Reports
- HSDC ADVISOR



Composite Data Products

- Pre-Agreed Upon
 Aggregate Data
 Products
- No Confidential Information







Hydrogen Vehicles



By 2009, 250+ mile range, 2000 hour fuel cell durability







Vehicles have been delivered and data collection has begun



Hydrogen Refueling Infrastructure



By 2009, <\$3.00/gge hydrogen, untaxed




Hydrogen Refueling Stations Opened in California, Michigan and Washington D.C.

Data Collection



Diverse Geography Addresses Four Key U.S. Climates



Cold, Moderate, Hot/Humid, Hot/Arid Climates



Hydrogen Locomotive and Front End Loader Vehicles Accomplishments



Accomplishments:

- Completed testing of hydrogen locomotive
- Completed detailed engineering design, review and risk assessment for front end loader
- Completed fabrication and testing of fuel cell power plant for front end loader
- Other subassembly fabrication in progress including metal hydride storage for front end loader



Task 2 – Hydrogen Infrastructure Power Parks



By 2008, 20,000 hour fuel-cell durability (stationary), 32% efficiency, \$1500/kW

By 2008, 68% efficiency (electrolyzer stack) and \$600/kW

Description

- Design and construct early refueling facilities on integrated renewable/fossil systems
- Document permitting requirements, lessons learned and safety plans
- Collect and disseminate operating data from different geographic regions



Task 2 – Hydrogen Infrastructure **Power Parks**



By 2008, 20,000 hour fuel-cell durability (stationary), 32% efficiency, \$1500/kW



Motor Vehicle Refueling

Refueling E	vents	
	Hydrogen	236
	CHyNG	717
	CNG	2,938
	Total	3,891
	Accidents	0
Fuel Disper	nsed*	
	Hydrogen	259 kg

259 kg 2,378 gge 14,218 gge



* Dispensed amounts are from credit card transactions.

CHyNG

CNG

Accomplishments:

- Power Park installed and operated that is capable of producing 60 kg/day and 400 kwhr/day. Utilize solar and biomass electrolysis systems. Dispense 5000 psi hydrogen at 99.995% (DTE)
- The hydrogen side of pilot park has a 99.33% availability during 26,000 ۲ calendar hours of operation and 8500 hours of electrolyser operation (APS)
- Fuel cell and ICE gen sets operating produced 9.6 MWH of power (APS) ٠
- Pearson 5 tpd gasifier using bagasse tested (Hawaii) •
- Initiated testing on Ballard and GM fuel cells (Hawaii) •



Task 3 – Natural Gas-to-H₂ Refueling Stations



By 2006, validate \$3.00/gge

Description

- Build and operate natural gas-to-hydrogen refueling station to collect data on reformer performance and reliability
- Validate the cost of H₂ produced including station operation and maintenance
- Disseminate data from refueling sites to verify component performance



Task 3 – Natural Gas-to-H₂ Refueling Stations

By 2006, validate \$3.00/gge

Accomplishments:

- Completed Phase 2 subsystem development for all components of an advanced SMR. Final system design efforts and equipment procurement initiated. Liquid hydrogen tank and blend and dispenser systems installed. (APCI)
- Completed subsystem and system designs. Second generation fuel processor built and tested. Developed hydrogen dispenser fill control algorithm. (GTI)
- Completed Phase 2 development of an autothermal cyclic reformer pilot scale reformer and PSA subsystem. Both systems have been operated to finalize Phase 3 system design. (GE)
- Autothermal reformer tested at SunLine to supply hydrogen for demonstration buses in revenue service. (Hydradix)
- Design and component testing completed on isothermal compressor. (APCI)









Task 4 – Co-Production of H₂ & Electricity



By 2005, validate 8¢/kWh and \$3.60/gge

Description

- Collect data on reformer and fuel cell performance, reliability and cost
- Identify the operation and maintenance requirements for the Energy Station
- Determine the economics for a large coproduction refueling station



Task 4 – Co-Production of H_2 & Electricity



By 2005, validate 8¢/kWh and \$3.60/gge

Accomplishments:

- Successfully demonstrated 2,000 hour run on hydrogen generator (Las Vegas)
- Installed and initiated operation of commercial fuel cell system (DTE)
- Designed and initiated procurement of second generation hydrogen generator (Penn. State)
- Go decision made to proceed with engineering development and preliminary design of high temperature fuel cell concept (APCI)
- 5 kW solid oxide fuel cell system design completed. Component assembly and testing initiated. (Chattanooga)
- Bus successfully operated on 30%/70% hydrogen/natural gas blend (Las Vegas)





Task 5 – Renewable H₂ Production Systems



By 2011, validate \$2.85/gge at the plant gate from biomass/wind or geothermal resource

Description

- Validate integrated systems and their ability to deliver hydrogen
- Collect data to verify component performance



Task 5 – Renewable H₂ Production Systems



By 2011, validate \$2.85/gge at the plant gate from biomass/wind or geothermal resource




Accomplishments:

- Completed construction and preliminary testing of biomass-to-hydrogen pyrolysis-reformer pilot plant (Clark Atlanta University)
- Identified potential co-products option (University of Georgia)
- Safety and component performance review completed (University of Georgia)
- PV hydrogen station design completed (UNLV)




Task 6 – Technical Analyses



Description

- Analyze early infrastructure deployment options
- Analyze advanced Power Parks for production of hydrogen and electricity

Calibration of FC polarization curve to APS data



<u>Accomplishments</u>

- Early hydrogen infrastructureanalysis completed forseveral scenarios
- Power Park validation analyses for several stations is completed



Future Work



Task 1Complete testing and analysis of generation1 vehicles and operation and analysis ofinfrastructure

Continue data collection on VTA, Hickam, AC Transit and SunLine buses

Complete front end loader test program

- Task 2 Complete the installation and operation of 3 power park projects
- Task 3 Complete validation of 3 natural gas to hydrogen refueling stations projected to produce hydrogen at less than \$3.00/gge



Future Work Continued



Task 4 Complete validation of energy station projected to produce hydrogen at less than \$3.60/gge and 8¢/kWh

Continue with high temperature coproduction systems

Task 5Complete 1000 hour durability and performance
tests of biomass pyrolysis system

Complete construction and testing of PV hydrogen refueling station

Task 6Complete analysis of power park systems and
define market applicability

Continue development of early infrastructure scenarios