

Integrated Short Contact Time Hydrogen Generator (SCPO)

2008 DOE H2 Program Annual Review Meeting

Ke Liu, Rick B. Watson, Wei Wei, Jin-ki Hong, Joel Haynes,
& Mark Thompson

GE Global Research Center

Wednesday, June 11, 2008

Theodore Krause
Argonne National Lab

Lanny Schmidt & Anders Larsen
Univ. of Minnesota

This presentation does not contain any proprietary or confidential information



imagination at work

Project ID # PDP17

Overview

Timeline

Project start date: 05/30/2005

Project end date: 10/31/2008

Percent complete: 90%

Budget

Total project funding

> DOE share: \$2.6M

> Contractor share: \$1.4M

Funding received in FY05: \$490K

Funding received in FY06: \$400K

Funding received in FY07 : \$1.37M

Funding received in FY08 : \$0

No-cost extension
granted to
10.31.08

Barriers

- Technical Barriers Addressed:
 - A. Cost of Fuel Processor
 - C. Operation and Maintenance (O&M)
 - D. Feedstock Issues
 - E. Catalyst sulfur tolerance & durability
- Technical Targets (2010):
 - Total Energy Efficiency (%LHV) > 75%
 - Total H₂ Cost \$2.00-\$3.00/gge H₂


Partners

- University of Minnesota
- Argonne National Lab



Objectives

The main objective of the SCPO project is the development of a low-cost, compact reforming technology that is fuel flexible; developed to operate on fossil fuels but adaptable to renewable fuels.



- This technology integrates three catalysts into a single compact reactor: catalytic partial oxidation (CPO), steam methane reforming (SMR), and water gas shift (WGS).
- Demonstrated via testing of high-pressure pilot-scale CPO, SMR and WGS reactors in GE Global Research's lab at Irvine, California.

Approach

Project Team



GE Global Research

Energy and Economic Analyses, HTS Catalyst Development, Pilot-Scale System Design/ Fabrication/Operation, and Overall Project Management



University of Minnesota

Short Contact Time Catalyst Identification, Preparation, and Parametric Testing

ARGONNE

Argonne National Lab


Catalyst Durability, Lining and Characterization

3-Year, \$4-Million Program to Develop a Compact Integrated Hydrogen Generator Based on SCPO Technology


Project Objective: To develop a compact hydrogen generator that can deliver H_2 at a cost of $< \$3.00/Kg$ with $> 75\%$ efficiency



Short Contact Time Catalyst Development



System Design and Analysis



Pilot-Scale System Design and Operation

Technical Approach


- Develop short contact time catalysts
- Design compact integrated reformer based on SCPO technology
- Demonstrate feasibility of the concept on a pilot-scale system

Anticipated Benefits

- Revolutionary, compact, highly efficient and low cost H_2 generation technology
- Applications in H_2 refueling stations and coproduction of H_2 and electricity with CO_2 separation

Program Deliverables

- Short contact time reforming and shift catalysts
- Pilot-scale H_2 generator meeting DOE targets




Development of SCPO Based Hydrogen Generator



imagination at work

SCPO & Warm Gas Cleanup 2007-2008 Major Milestones

Catalytic Partial Oxidation (CPO)




- Prepared catalyst test samples for in-house and Premix tests and compared to commercial formulation
- Completed 40 experimental runs in CPO system up to 500kh⁻¹ GHSV and 275 psig. (70Kg/day H₂ production level)
- Completed screening, spatial profiling, and sulfur exposure tests
- Integrated results into modeling efforts for cost analysis and Gas Turbine integration systems analysis




Premix design for CPO/Gas Turbine




- Designed, fabricated reactor & premixer
- Retrofitted experimental facility with reactor
- Completed test matrix from 250-500 kh⁻¹ GHSV at different steam concentrations
- Achieved near equilibrium H₂ production



Relative Test Size





Steam Methane Reforming (SMR)



- Completed design, construction and shakedown of combined SMR/WGS system in 2007
- Completed precious metal and nickel based SMR catalyst screening, long term testing, and sulfur tolerance at Argonne National Lab
- Completed SMR system large scale demonstrations at FCL
- Integrated results into heat transfer modeling




Water Gas Shift (WGS)



Residence Time (s); Proportional to vessel size & catalyst loading

- Completed design, system modeling and reactor fabrication
- Completed WGS catalyst screening at Argonne National Lab
- Completed aggressive HAZOP review for 2007 and baseline WGS catalyst testing


Distributed Hydrogen Fueling Station Using GE SCPO Technology




imagination at work

SCPO Cost of Hydrogen Estimation Approach

Conceptual Design



Process Evaluation (Assumptions)



H2A Model



Updated Cost of Hydrogen:
\$3.025/kg

Updated CPO Performance w/ Experimental Data

	Prior Assumption	Experimental
SCPO Conversion	99.56%	98.18%
SMR Conversion	74.16%	79.10%
Production Unit Hydrogen Efficiency (%)	73.0%	75.4%
Production Step Efficiency (%)	70.3%	72.5%
Total System Efficiency (%)	66.5%	68.5%

Catalyst & Process R&D



CTQ

DOE deliverables met in 2008

Project continues to develop and demonstrate CPO catalyst technology

Cost of Hydrogen Updates

	Prior Assumption	Experimental
SCPO Conversion	99.56%	98.18%
SMR Conversion	74.16%	79.10%
Production Unit Hydrogen Efficiency (%)	73.0%	75.4%
Production Step Efficiency (%)	70.3%	72.5%
Total System Efficiency (%)	66.5%	68.5%
Hydrogen Selling Price and Cost Contributions (Year 2005 \$)		
	Previous H2A	Updated H2A
Required Hydrogen Selling Price (\$(Year 2005)/kg of H2)	\$3.052	\$3.025
Capital Costs (\$/kg of H2)	\$1.384	\$1.384
Fixed O&M (\$/kg of H2)	\$0.578	\$0.578
Feedstock Costs (\$/kg of H2)	\$0.828	\$0.802
Other Raw Material Costs (\$/kg of H2)	\$0.000	\$0.000
Byproduct Credits (\$/kg of H2)	\$0.000	\$0.000
Other Variable Costs (including utilities) (\$/kg of H2)	\$0.262	\$0.261

Aspen model of the SCPO system was updated using the SCPO and SMR experimental data → Updated H2A cost analysis

GE Test Facilities



Controlled and Monitored Gas Delivery



Steam Methane Reforming (SMR)

Two photographs showing SMR equipment. The left image features a red robotic arm positioned next to a vertical reactor column. The right image shows a close-up of the reactor column's top section.

Catalytic Partial Oxidation (CPO)





Two photographs showing CPO equipment. The top image is a close-up of a yellow reactor vessel. The bottom image shows a control console with multiple monitors and a robotic arm.

Water-Gas-Shift (WGS)


Two photographs showing WGS equipment. The left image shows a red robotic arm next to a vertical reactor column with a 'CAUTION HOT' sign. The right image is a close-up of the reactor column's top section.

Task 1 Premix CPO and Sulfur Tolerant Catalysts


CPO Catalyst Performance Versus Structure



Spatial Profiles Inside the Foam Catalyst






- Developed a system that allows to *in situ* sampling in a system with very high temperature and species gradients
- Unprecedented spatial resolution ($\sim 300\mu\text{m}$) on the order of the characteristic length of the support
- Sampling method introduces minimal disturbance in flow. Sample rate 10ml/min, total flow 5000ml/min
- Analysis is done by mass spectroscopy which is continuously calibrated by gas chromatography









 The effect of pressure is not great



Constant Inlet Velocity



 Oxidation zone varies as expected with changes in pressure



Mass transfer effects



$$Sh = \frac{k^m L}{\mathcal{D}} = c Re^a Sc^b$$


$$Sh \propto \left(\frac{1}{\sqrt{T}} \right)^a$$

$$-\frac{dY_{O_2}}{Y_{O_2}} = \frac{S k_{O_2}^m}{V u} dz$$

$$z = \ln \left(\frac{1}{f} \right) \frac{V \overbrace{\bar{u}}^{\text{Constant}}}{S k_{O_2}^m}$$







$$z \propto \frac{P}{T^{\frac{3}{2} - \frac{1}{2}a}} \sim P$$

🦉 Point of 50% oxygen conversion is predicted



CPO short term life testing followed by mass spec profiling

75 hour life test of GE baseline catalyst: 80 PPI pre-capillary drilled, L/D=0.65
 Conditions: 500,000 h⁻¹ GHSV, S/C=1, O₂/C=0.67



No significant changes seen through catalyst profile after 75 hours online with no sulfur;
 However, profiling shows the catalyst seems to be losing steam-reforming capability most likely due to phase transformations in the γ -alumina wash coat.


Effect of Sulfur on CPO





UoMn data shows that sulfur inhibits the steam reforming zone, but *is steady over 50 hours of testing with CH₃SH*

GHSV $1.4 \times 10^5 \text{ h}^{-1}$. C/O=1.

	0 ppm	14 ppm S	28 ppm S
X_{CH_4}	83%	68%	65%
X_{O_2}	100%	100%	100%
S_{H,H_2}	89%	79%	76%
$S_{C,CO}$	91%	90%	88%
S_{C,CO_2}	9%	9%	9%



Longer term CPO performance with sulfur





Initial step-change loss in performance with sulfur.

Catalyst temperature rising with time

Activity returned with increase in pressure

Methane turnover and hydrogen formation in CPO with and without sulfur:


GE baseline formulation



We are evaluating step-loss in performance as well as longer term deactivation


Optimizing start/stop CPO behavior in the presence of sulfur

CPO performance of GE baseline formulation using 20 ppm S simulated natural gas (Steamed stop/starts)






We are optimizing shutdown and start-up procedures to maintain performance

Task 2 & 3 SMR & Shift Experiments





Steam Methane Reforming Results


225 psig
equilibrium curve
3:1 H₂O/C



Task 3. Water Gas Shift Catalyst & Reactor Designs



Completed low GHSV WGS catalyst performance and heat balance tests in 2007



ANL – FY07 and 08 Workscope and Status

Steam reforming catalyst evaluation and development

- > Precious metal catalysts (3 catalysts from vendor A; 2 catalysts from vendor B; and 3 catalysts from Argonne)
 - *Activity* (Status: completed)
 - Low temperature SMR conditions
 - High temperature SMR conditions
 - *Durability* (Status: completed)
 - Low temperature SMR conditions
 - *Sulfur-tolerance* (Status: completed)
 - Low temperature SMR conditions at 5 and 20 ppm H₂S
 - CPO extended sulfur test
- > Base metal catalysts (4 catalysts from two commercial vendors)
 - *Activity* (Status: complete)
 - *Durability* (Status: complete)



Water-gas shift catalyst evaluation

- > Precious and base metals (1 PM and 1 base metal catalyst, two different vendors)
 - *Activity* (Status: complete)
 - *Durability* (Status: in progress)


WGS and SMR Catalysts Were Evaluated for Activity and Durability

PM SMR Catalysts evaluated under CPO conditions

Temperature profile observed for a commercial PM SMR catalyst operating under CPO conditions



Activity - High Temp WGS Conditions



Activity was evaluated as a function of steam-to-carbon ratio (total carbon equal to the sum of CO, CO₂, and CH₄), temperature, and space velocity.

Durability was evaluated for SMR under CPO conditions, not acceptable for sulfur tolerance.

Identified the catalyst that exhibits the best combination of activity and durability for both SMR and WGS and validated kinetics.

Summary & Highlights

- Project extended to Oct. 31, 2008 for refined economics and CPO catalyst testing
- Completed SMR demonstration and kinetics validation
- Completed WGS demonstration and most of the kinetic data validation
- High-P CPO data obtained from our high-P CPO unit continues to synergize with UoMn characterization work.
- Initial work on sulfur tolerance is promising and we are characterizing activity losses
- Completed cost analysis using GE's process model & DOE's H2A model
Economic analysis has been refined with new experimental data
- Base case catalysts identified, Reactor sizing / design completed.
- HEX technology tradeoff completed, HEX technology selected, design completed
- Control strategy, start-up & shut-down procedure being developed.

Conclusions & Recommendations

- ❑ SCPO will be a leading technology for H₂ production from NG. It is a cost-effective distributed H₂ production technology based on the economic analysis of different H₂ production technologies. With minor modification, we can extend the feed to gasoline, diesel, ethanol & methanol.
- ❑ The technologies developed in this program has good synergies with application in fuel blending, NGCC with CO₂ capture, SOFC & syngas production for GTL....

Refinement of the system analysis for updated costs and further development of the CPO catalyst (sulfur tolerance) will be the focus points for the remainder of the project year.