

# Low-cost Co-Production of Hydrogen and Electricity

Fred Mitlitsky

Bloom Energy Corporation

May 22, 2009

Project ID  
#FC\_46\_Mitlitsky

# Overview

## Timeline

- Contract signed: November 13, 2006
- Contract end date: December, 2009
- To date: 65% complete

## Budget

- Total project funding: \$4,973,601
  - DOE share: \$2,480,000
  - Contractor share: \$2,493,601
- Funding received in FY08: \$933,153
- Estimated FY09 funding: \$1,435,838

## Barriers addressed

- Distributed hydrogen production from natural gas: purity, volume, cost
- Fuel Cells: durability, performance, cost

## Partners

- Bloom Energy: Planar SOFC system, hydrogen testing, and project management
- Udelhoven Oilfield System Services, Anchorage, AK: General Construction
- H2 Pump LLC, Latham, NY: Equipment
- Giner Electrochemical Systems, LLC, Newton, MA: Equipment
- Univ. of Alaska, Fairbanks, AK: Independent Validation

# Objectives

Overall	<ul style="list-style-type: none"><li>• Demonstrate cost-effective, efficient, reliable and durable planar solid oxide fuel cell (PSOFC) systems for stationary applications</li><li>• Determine the feasibility of a delivered cost of hydrogen below \$2.50 per gge</li><li>• Determine the economics of hydrogen and electricity co-production for comparison to stand alone hydrogen production facilities</li></ul>
2008	<ul style="list-style-type: none"><li>• Complete site construction</li><li>• Install, commission &amp; remotely operate PSOFC system</li><li>• Hydrogen pump production system build, test &amp; optimization</li><li>• Combined PSOFC &amp; hydrogen production system testing</li><li>• Partial pressure swing adsorption (PPSA) prototype design</li><li>• Hydrogen cost analysis using the DOE H2A model</li></ul>
2009	<ul style="list-style-type: none"><li>• Complete PSOFC system demonstration</li><li>• Complete hydrogen production demonstration</li><li>• Complete PPSA build, test &amp; investigation</li><li>• Complete cost and economics analysis</li></ul>

# General Approach

- Build and test a planar solid oxide fuel cell electricity generating system that runs on natural gas
  - One year operating demonstration at commercial site
- Evaluate hydrogen production systems
  - Select one option for in-system demonstration
  - Procure, integrate & test
- Demonstrate PSOFC co-production of electricity and hydrogen
- Independent, third party validation (University of Alaska, Fairbanks)
- Economic analysis

# Tasks

1. Site selection, design & build
2. Design integration of hydrogen production module with PSOFC
3. H<sub>2</sub> Pump, PSOFC system builds & in-lab testing
4. PSOFC in-field demonstration  
Hydrogen production demonstration
5. Decommissioning

# Technical Accomplishments/Progress/Results

- Alaska site build completed with partners
  - Udelhoven Oilfield System Services
    - PDC Engineering
    - Johnson Controls
  - Chugach Electric Cooperative
  - Enstar Natural Gas
  - City of Anchorage
- PSOFC system installed and operational – key metrics achieved
- Full scale hydrogen pump integrated with PSOFC
  - Commercial anode exhaust hydrogen separation and recycle solution chosen (H2 Pump) for integration & testing with PSOFC
- Partial pressure swing adsorption (PPSA) design & prototype testing in parallel (Giner)
- Hydrogen cost analyzed using the DOE H2A model

# PSOFC Field Demonstration: Site Build

Site prior to PSOFC install



PSOFC installation



Electrical/Gas Inputs, Air Outputs



Building Air Handling Unit



Air Intake





# Air Handling Unit Inlet with Hoarfrost





# PSOFC System Operation Objectives

- 25 kW power
- Operation on natural gas
- Operate at 480V
- Grid parallel operation
- Remote monitoring
- 70% uptime over one year demonstration
- 45% peak net electric efficiency in electric-only mode

# 25kW PSOFC System 1C

## Operating Statistics

25kW Operation	System 1C	
Average AC Efficiency	45.9	%
Peak AC Efficiency	51.1	%
Total Energy Output	48004	kWhrs
Total Fuel Consumption	10351856	L
Peak AC Power	25.9	kW
Hrs On-Site	2191	Hrs
Uptime	2178	Hrs
Load Hrs	2166	Hrs
Availability On Load	98.9	%
Availability at 20.0kWac+	93.6	%
Grid Faults	4	
System Faults	3	

*-Ship 11/16/08 -Start 12/3/08 -Run data through 3/5/09*

# 25kW PSOFC System 1D


## Operating Statistics

<b>25kW Operation</b>	<b>System 1D</b>	
Average AC Efficiency	46.1	%
Peak AC Efficiency	48.9	%
Total Energy Output	47538	kWh
Total Fuel Consumption	10183941	L
Peak AC Power	25.4	kW
Hrs On-Site	2191	Hrs
Uptime	2182	Hrs
Load Hrs	2177	Hrs
Availability On Load	99.4	%
Availability at 20.0kW <sub>ac</sub> +	93.2	%
Grid Faults	3	
System Faults	3	

*-Ship 11/16/08 -Start 12/3/08 -Run data through 3/5/09*



# System 1D Power Output



*Run data 12/3/08 through 3/5/09*


# Fault Analysis

- Six service calls 12/3/08 - 3/5/09
- #1 fault condition: Anchorage weather
  - Water pump & water flow meter: not rated for  $<0^{\circ}\text{C}$
  - Building thermal control shutdown when air intake clogged with hoarfrost
- Components upgraded
  - Power electronics
  - Mass flow controller
  - Anode recycle blower



# Blower Studies

- Blower research and development to improve system efficiency and reliability through reduction of parasitic losses and simplified installation
- Development of anode recycle blower capable of high temperature ambient/media
  - Hydrogen
  - Carbon Dioxide
  - Steam
  - Carbon Monoxide
- Started with a commercially available air blower
  - Collaboration with vendor and their local university
  - Applying CFD to develop a series of modifications to make it suitable for operation as an anode recycle blower






# Low-Cost Co-Production of Hydrogen and Electricity

Purify hydrogen from anode exhaust stream

- Electrochemical H<sub>2</sub> Pump
- Partial Pressure Swing Adsorption




# 25kW PSOFC Demonstration with H2 Pump

- Two operational modes
  - Hydrogen recycle
  - External hydrogen delivery
- SOFC operation at 95% fuel utilization in recycle mode
- 2000 hours test duration, with < 5% performance degradation of hydrogen production (19 kg/day max production)

H2 Pump with 120 cell stack  
Operating temperature: 150C – 180C  
Product hydrogen pressure: <5 psig




# H2 Pump Test Demonstrated 19kg/day & High Purity



- Improved plumbing, preparation & measurement capability are needed to demonstrate hydrogen purity exceeding six 9's

# Full Sized PPSA Prototype Build

- 25kW sized PPSA unit from Giner expected Q2 '09
- No water gas shift required
- Low parasitic electrical power
- Anode exhaust to be separated
  - Flow rate: 99 slpm
  - Temperature: 30C
  - Supply pressure: 5 inches water column
  - H<sub>2</sub> (29.3%), CO<sub>2</sub> (66%), H<sub>2</sub>O (3.4%) & CO (1.3%)
- PPSA effectiveness
  - 80% fuel recovery (CO, CH<sub>4</sub>, H<sub>2</sub>)
  - 95% CO<sub>2</sub> separation



# H2 Cost Analysis Using DOE H2A Model

	Original Proposal (BE model)	Current Analysis (H2A Model)
Installed Capital Cost	\$1,500 / kW	\$1,500 / kW
Overall <b>System</b> Efficiency	56%	56%
Net <b>Electrical</b> Efficiency	33%	33%
<b>NG Cost</b>	\$8 / mmbtu	AEO 2007
<b>Capacity Factor</b>	90%	98%
<b>H2 / Year</b>	50,192 kg	54,656 kg
<b>Electrical Output</b>	200kW	200kW
<b>Delivered cost of H2/gge</b>	<b>\$4.82</b>	<b>\$4.53</b>

*BE & H2A models are very consistent; differences are in assumed capacity factor*

# H2 Cost Analysis Adding Value of Electricity

	Original Proposal (BE model)	Current Analysis (H2A Model)
Delivered cost of H2/gge	\$4.82	\$4.53
Value of Electricity	\$0.12 / kWh	\$0.12 / kWh
Electrical output	1,576,800 kWh / year	1,716,960 kWh / year
Value of annual output	(\$167,360)	(\$182,240)
H2 / Year	50,192 kg	54,656 kg
Value of Electricity / kg H2	(\$3.77)	(\$3.77)
H2 cost, net/gge @ 300 psi	<b>\$1.26</b>	<b>\$0.97</b>

*Projections are consistent with DOE delivered cost of H2 goals*

# Future Work

- Complete one year demonstration of PSOFC system
- Complete demonstration of co-production of electricity and hydrogen
  - Complete PSOFC & H2 Pump 2000 hour test
  - Third party validation of volume & purity
- Complete PPSA prototype test
- Complete cost modeling




# Supplemental Slides



*Photograph by R. Clucas, courtesy Alaska Volcano Observatory, USGS*


Mt. Redoubt volcano eruptions shutdown Anchorage Airport in March 2009

# System 1C Efficiency



*Run data 12/3/08 through 3/5/09*

# System 1D Efficiency



*Run data 12/3/08 through 3/5/09*