

Technoeconomic Boundary Analysis of Photoelectrochemical (PEC) Hydrogen Producing Systems

Brian D. James

Directed Technologies, Inc.

May 20, 2009

Project ID #

PD_23_James

Overview

Timeline

- Start: May 2008
- End: June 2009
- Percent Complete: 90%

Budget

- Total project: \$190,718.57
- FY08: \$190,718.57
- FY09: N/A
- No Contractor Share

Barriers

- AD. Systems Design and Evaluation
- AE. Diurnal Operation Limitations

Partners

- DOE PEC Working Group
(DOE plus 12 organizations)

Relevance


Project Objectives

- Perform Economic & Technical Analysis of H₂ producing systems
 - Create photoelectrochemical (PEC) H₂ production conceptual system designs
 - Colloidal Suspension
 - Photoelectrode
 - Hydrogen Cost Calculations
 - System capital costs
 - Levelized H₂ costs
- Identify key factors affecting cost estimates

Design Features


- Advancing implementation of new technology by designing physical systems tailored to PEC materials
- Design of gas collection system for continuous operation
- Design of solar collection for maximum sunlight conversion

Approach







Colloidal Suspension Reactor Concept

Plant Capacity = 1 TPD Module x 10



| | | |
|---|---|---|
| Pure Water Splitting | 10% Solar-to-Hydrogen Efficiency (baseline) | Reactant contained in Shallow Bags |
| Coated Nanoparticles in 0.1M KOH Electrolyte Solution | Product Gas after condensor: 99% H_2 1% H_2O | LDPE fibrous mat is liquid permeable "window" between beds |
| | O_2 not collected, released to atmosphere | 10 TPD H_2 output from ten linked 1 TPD H_2 modules |

Colloidal Suspension Reactor Design



1 Baggie System = 2 full baggies (200 ft x 6.6 ft x 1.5 ft) + 2 half baggies (200 ft x 3.3 ft x 1.5 ft)
 1 TPD Module (at 10% efficiency) = 368 Baggie Systems over 43 acres
 10 TPD Plant Capacity = Ten x 1 TPD modules


Plant Design: 1 TPD Module

Effective Reactor Cost: \$9/m²

Nanoparticle Colloidal Suspension Concept

| Parameter | Value |
|----------------------|--------------------------------|
| Base Material | Fe ₂ O ₃ |
| Base Particle Size | 40 nm |
| Coating | TiO ₂ |
| Coating thickness | 5 nm x 2 layers |
| Solar Efficiency | 10% |
| Suspension Beds | 134,667 m ² |
| Lifetime | 5 yrs |
| Cost (nanoparticles) | \$304/kg |

Capital Expenditures



Bill of Materials

| Description | Unit Size | Units | Unit cost | Qty Req'd | Total Cost |
|--------------------------------|-----------|----------|--------------|-----------|------------|
| Baggie Subassembly | | | | | |
| Baggie Cost | 1 | Module | \$ 839,400 | 1 | \$839,400 |
| Levelling of Area | 1 | Acre | \$ 3,896.00 | 36 | \$140,256 |
| Forklift | 1 | Forklift | \$ 18,571.00 | 1 | \$18,571 |
| Coated PEC Microparticles | 1 | kg | \$ 304.00 | 142 | \$43,271 |
| Miscellaneous Piping | | | | | \$104,150 |
| Make-up Water Pump | 1 | pump | \$ 212.50 | 1 | \$213 |
| Gas Capture Subassembly | | | | | |
| Compressor | 23 | kgH2/hr | \$ 9,233.00 | 23 | \$ 208,783 |
| PSA | | | | | \$ - |
| Piping - 4" | 1 | ft | \$6.18 | 2140 | \$13,225 |
| Piping - 1" | 1 | ft | \$1.00 | 72 | \$72 |
| Control System | | | | | |
| PLC | | | \$ 2,000.00 | 1 | \$2,000 |
| Control Room | 1 | ft2 | \$ 50.00 | 160 | \$8,000 |
| Control Room Wiring Panel | 1 | | \$ 3,000.00 | 1 | \$3,000 |
| Raceway wiring Panel | 1 | | \$ 146.00 | 36 | \$5,256 |
| Computer and Monitor | 1 | | \$ 1,500.00 | 1 | \$1,500 |
| Labview Software | 1 | | \$ 4,299.00 | 1 | \$4,299 |
| Level Indicators | 1 | | \$ 3,000.00 | 36 | \$108,000 |
| Pressure Sensors | 1 | | \$ 4,700.00 | 36 | \$169,200 |
| Hydrogen Area Sensors | 1 | | \$ 5,500.00 | 36 | \$198,000 |
| Oxygen Area Sensors | 1 | | \$ 5,500.00 | 36 | \$198,000 |
| Hydrogen Flow Meter | 1 | | \$ 5,500.00 | 1 | \$5,500 |
| Instrument Wiring | 1 | ft | \$ 0.02 | 193,350 | \$3,751 |
| Power Wiring | 1 | ft | \$ 0.02 | 192,150 | \$3,723 |
| Conduit | 1 | ft | \$ 0.58 | 4,810 | \$2,789 |



Effective System Cost: \$15/m²

System Initial Cost \$ 2,080,963

Colloidal Suspension Results: 10 TPD Plant

| Sensitivity Analysis Parameters | | |
|---------------------------------|---------------|-------------------|
| Efficiency | Particle Cost | Particle Lifetime |
| 5% | 0.5x | 1 Year |
| 10% | 1x | 5 Year |
| 20% | 30x | 10 Year |


Baseline Conditions



Baseline Cost = \$3.56/kg H₂

H₂ cost estimated at ~\$3.50/kg but cost is highly dependant on nanoparticle material system which is currently undefined

Photoelectrode Concept: Fixed Flat Plate



(Not to Scale)

30° fixed angle to horizon

| | | |
|--|--|---|
| 1.1x factor on horizontal insolation to reflect 30° fixed angle to horizon | 10% Solar-to-Hydrogen Efficiency (Baseline) | H ₂ compression to 300psi (external compressor) |
| 0.1M KOH Electrolyte Solution | 100% H ₂ recovery; Inherent separation of H ₂ and O ₂ | Plexiglass window, 95% photon transmittance |
| | O ₂ not collected, released to atmosphere | 10 TPD H ₂ from linked 1 TPD (net) H ₂ /day modules |

Multi-layer PEC Electrode Cost Analysis:

Based on DFMA analysis
and analogy to PV cell cost

FASST™, Heliovolt

- Proprietary printing process
- Heliovolt patented processes claim to cut PV coating times down by a factor of 100 to 6 minutes per cell
- Reported PV cell efficiencies of 12.2%, using CIGS (copper indium gallium selenide) thin-film technology

Magnetron Sputtering

- Thin Film:
 - three 2 μ m layers at \$300/kg (70% yield)
 - three 2 μ m layers at \$100/kg (70% yield)
 - 2 mil 310 SS substrate at \$4/m²
- Deposition Machine:
 - \$1.5M Magnetron Sputtering machine
 - 2.5 nm/s deposition rate
 - 1m x 2.13 m target size
- Cost: (DFMA Analysis) \$246.96/m²

Roll Printing, Nanosolar



- Solar cell printing rate of 30 m/min
- Goal PV cell efficiency of ~ 14% using CIGS
- Nanosolar PV price projection: (at 14% effic.)
 - Panels at \$0.99/Watt cells => \$139/m²
 - “Manufac. Cost” at \$0.30/Watt => \$42/m²

Ink Deposition

- Thin Film:
 - three 2 μ m layers at \$188/kg (90% yield)
 - three 2 μ m layers at \$278/kg (90% yield)
 - 2 mil 310 SS substrate at \$4/m²
- Deposition Machine:
 - \$870K Verti-Coater System
 - 10 m/min line speed
 - 1m web width
- Cost: (DFMA Analysis) \$25.73/m²

Selected Thin Film PEC element baseline cost of \$100/m²
with a \$30-\$150/m² spread for parametric analysis.

Photoelectrode System Parameters




PV Field

Photoelectrode Cell Concepts

| Parameter | Value |
|------------------------------------|----------------------|
| Transparent Anode | |
| Multi-Layer Thin film PV Cell: | |
| - High Bandgap | 1.5 – 2.0 eV |
| - Low Bandgap | 1.0 – 1.5 eV |
| Stainless Steel Cathode Substrate | 2 mil thickness |
| Pressure | 1 atm |
| Solar-to-H ₂ Efficiency | 10% |
| Lifetime | 10 yrs |
| Cost (baseline) | \$100/m ² |


Fixed Panel Plant Design

1 TPD Module



10 TPD Plant = 10 x 1 TPD Modules
 1 TPD Module = 27 acres (14 acres of cells)
 14 acres = 300 PV Fields = 28,995 cells

Cost Breakdown \$/Subassembly



Capital Expenditures

Effective Reactor Cost: \$143/m²

Bill of Materials for 1 TPD Module

| Description | Unit Size | Units | Unit cost | Qty Req'd | Total Cost |
|--------------------------------|-----------|-----------------|---------------|-----------|--------------|
| Reactor Bed Subassembly | | | | | |
| Thin Film PV Cell | 1 | m ² | \$ 100.00 | 57,990 | \$ 5,799,043 |
| Plexiglass Window | 1 | m ² | \$ 15.00 | 63,789 | \$ 956,842 |
| Frame | 1 | m ² | \$ 20.00 | 57,990 | \$ 1,159,809 |
| Frame Assembly | 1 | m ² | \$ 5.00 | 57,990 | \$ 289,952 |
| Manifold Piping | 0.5 | in | \$ 0.52 | 186619 | \$ 97,042 |
| Collection Piping | 0.5 | in | \$ 0.52 | 33350 | \$ 17,342 |
| Column Collection Piping | 2 | in | \$ 2.12 | 3400 | \$ 7,208 |
| Final Collection Piping | 3 | in | \$ 4.31 | 200 | \$ 862 |
| Gas Capture Subassembly | | | | | |
| Compressor | 23 | kgH2/hr | \$ 9,233.00 | 23 | \$ 208,783 |
| Condensor/HX #1 | 1 | | \$ 123,000.00 | 1 | \$ 123,000 |
| Condensor/HX #2 | 1 | | \$ 65,300.00 | 1 | \$ 65,300 |
| Control System | | | | | |
| PLC | 1 | | \$ 3,000.00 | 1 | \$ 3,000 |
| Control Room | 1 | ft ² | \$ 2.00 | 8,763 | \$ 17,527 |
| Control Room Wiring Panel | 1 | | \$ 3,000.00 | 1 | \$ 3,000 |
| Raceway wiring Panel | 1 | | \$ 146.00 | 15 | \$ 2,190 |
| Computer and Monitor | 1 | | \$ 1,500.00 | 1 | \$ 1,500 |
| Labview Software | 1 | | \$ 4,299.00 | 1 | \$ 4,299 |
| Level Indicators | 1 | | \$ 3,000.00 | 15 | \$ 45,000 |
| Pressure Sensors | 1 | | \$ 4,700.00 | 15 | \$ 70,500 |
| Hydrogen Area Sensors | 1 | | \$ 5,500.00 | 15 | \$ 82,500 |
| Oxygen Area Sensors | 1 | | \$ 5,500.00 | 15 | \$ 82,500 |
| Hydrogen Flow Meter | 1 | | \$ 5,500.00 | 1 | \$ 5,500 |
| Instrument Wiring | 1 | ft | \$ 0.02 | 43,095 | \$ 836 |
| Power Wiring | 1 | ft | \$ 0.02 | 42,525 | \$ 835 |
| Conduit | 1 | ft | \$ 0.58 | 3,980 | \$ 2,308 |



Effective System Cost: \$156/m²

System Initial Cost \$ 9,046,667

Photoelectrode Results

| Sensitivity Analysis Parameters | | |
|---------------------------------|----------------------|--------------------|
| Efficiency | Film Cost | Thin Film Lifetime |
| 5% | \$30/m ² | 5 year |
| 10% | \$100/m ² | 10 year |
| 20% | \$150/m ² | 20 year |

Baseline Conditions




Baseline Cost = \$10.20/kg

Hydrogen Cost ~\$10/kg but PEC system benefits directly from PV cell cost reductions. Cost Reduction to ~\$5.50/kg H₂ is quite possible.

Other PEC Variants


- **Colloidal Suspension, Single Bed**

- Same Nanoparticle Material System
- Fewer beds, Lower Capital Cost
- Mixed H_2/O_2 Output Gas (potential combustion issue)



- **Photoelectrode, Tracking Concentrator**

- Higher efficiency (15% baseline, 25% max)
- Reduced Active PV area
- 300 psi (or higher) operation, No Compressor
- Lower Capital Cost, More complex (solar tracking)



| Costs | Single Bed | Concentrator |
|-----------------------------|-------------------------|---------------|
| Capital (\$) (1 TPD Module) | \$1.0M to \$2.7M | \$5.94M |
| H2A H ₂ Cost | \$1.63 to \$3.18 Per kg | \$3.98 Per kg |

Collaborations

| Collaborator | Organization | Role | Expertise |
|------------------------------------|--------------------------------|---------------------------------------|--|
| Photoelectrochemical Working Group | DOE + DOE Funded Organizations | Material Systems, Directional support | All PECs |
| Eric Miller | University of Hawaii | System Concept Exploration | PEC electrode systems, Comprehensive PEC R&D awareness |
| Eric McFarland | UC-Santa Barbara | System Concept Exploration | Colloidal Suspensions |
| Tom Jaramillo | Stanford | System Concept Exploration | Colloidal Suspensions |

Proposed Future Work

Current Contract

- Prepare Final Report

Future Work

- Refine cost projection for new material systems & fabrication methods
- Explore new system concepts
 - Have only looked at simplest most straightforward applications
 - Investigate other concepts which may have merit:
 - HBr/Br₂ systems
 - Waste-water as feedstock
 - Electrolyzer mode (PEC with electrical bias)
 - Detailed system definition of Low Cost Concentrator PEC

Summary

- **Photoelectrochemical (PEC) H₂ Production**

- 12.2% solar-to-H₂ efficiency previously demo'd in lab but with short lifetime
- Research is focused on identifying & fabricating appropriate long-lasting material systems

- **Technoeconomic Boundary Analysis conducted**

- Evaluate system concepts
- Estimate \$/kg of resulting PEC H₂
- Provide system context to researchers
- Better understand cost drivers & sensitivities

- **Two Primary Concepts explored**

- Colloidal Suspension Systems

- Separate beds for H₂ and O₂ production
- 10% STH appears feasible
- “Baggie” concept feasible but inter-bed diffusion needs further study
- Expected price: \$3.56/kg_{H₂} (Potential range: \$2.03-\$7.63/kg)

- Photoelectrode Systems


- Analogous to PV panels but suspended in water/KOH electrolyte
- Benefits from PV panel cost reduction in Solar Cell Industry
- 10% STH feasible (possibly 25%)
- Expected price: \$10.20/kg_{H₂} (Potential range: \$5.61-\$19.39/kg)
- Concentrating Photoelectrode systems offer lower price \$3.98/kg_{H₂} but with increased complexity

- **Alternate PEC concepts worth exploring**

- **Extensive collaboration/coordination with DOE PEC Working Group**

Backups

Photoelectrode Concentrator Concept



- Solar Concentration:
10:1 baseline
20:1 achievable

- 0.1M KOH Electrolyte Solution
- Can easily add PEM membrane if needed for ion separation
- 1.32x factor on horizontal insolation to include combined effects of tracking gain and diffuse sunlight loss

- Solar-to-Hydrogen Efficiency
15% baseline
25% max

- 100% H₂ recovery; Inherent separation of H₂ and O₂
- O₂ not collected, released to atmosphere



- 10 TPD H₂ from linked 1 TPD H₂/day modules

- Plexiglass window:
90% photon transmittance
circular section to reduce stress
- Reduced size PEC cell allows operation at 300psi and higher
→ no compressor required

Concentrator Plant Design

Bill of Materials for 1 TPD Module

Sized for 1000kgH₂/day Module.



| | | | | | | | | | |
|--|--------|----------------|---|----------------|----|----------|----------|----|---------------------|
| Tracking & Concentrating | 34,007 | m ² | 1 | m ² | \$ | 89.00 | 34,007 | \$ | 3,026,599.33 |
| PEC Subassembly 3B -10: 1 & 300 psi | | | | | | | | | |
| Area ratio | 10 | : | 1 | | | | | | |
| Pressure | 300 | psi | | | | | | | |
| PEC element | 3,401 | m ² | 1 | m ² | \$ | 150.00 | 3,401 | \$ | 510,101.01 |
| Plexiglass Window | 3,401 | m ² | 1 | m ² | \$ | 37.00 | 3,401 | \$ | 125,824.92 |
| Frame | 3,401 | m ² | | | \$ | 20.00 | 3,401 | | |
| Assembly | 3,401 | m ² | | | \$ | 5.00 | 3,401 | | |
| Manifold Piping | 0.5 | in | 1 | 1 | ft | | 131324.5 | \$ | 68,288.73 |
| Collection Piping | 0.5 | in | 1 | ft | | 0.52 | 24150 | \$ | 12,558.00 |
| Column Collection Piping | 2 | in | 1 | ft | | 2.12 | 3400 | \$ | 7,208.00 |
| Final Collection Piping | 3 | in | 1 | ft | | 4.31 | 200 | \$ | 862.00 |
| Gas Capture Subassembly | | | | | | | | | |
| Compressor | | | | | | | | \$ | - |
| Drying System | | | | | | | | \$ | - |
| Controls | | | | | | | | | |
| PLC | | | | | \$ | 3,000.00 | 1 | \$ | 3,000.00 |
| Control Room | | | | 1 | m | | | \$ | 17,526.78 |
| | 8,763 | m | | | \$ | 2.00 | 8,763 | | |
| Control Room Wiring Panel | | | | | \$ | 3,000.00 | 1 | \$ | 3,000.00 |
| Raceway wiring Panel | | | | | \$ | 146.00 | 1 | \$ | 146.00 |
| Computer and Monitor | | | | | \$ | 1,500.00 | 1 | \$ | 1,500.00 |
| Labview Software | | | | | \$ | 4,299.00 | 1 | \$ | 4,299.00 |
| Level Indicators | | | | | \$ | 3,000.00 | 1 | \$ | 3,000.00 |
| Pressure Sensors | | | | | \$ | 4,700.00 | 1 | \$ | 4,700.00 |
| Hydrogen Area Sensors | | | | | \$ | 5,500.00 | 1 | \$ | 5,500.00 |
| Oxygen Area Sensors | | | | | \$ | 5,500.00 | 1 | \$ | 5,500.00 |
| Hydrogen Flow Meter | | | | | \$ | 5,500.00 | 1 | \$ | 5,500.00 |
| Instrument Wiring | | | | | \$ | 0.02 | 1,725 | \$ | 33.47 |
| Power Wiring | | | | | \$ | 0.02 | 1,575 | \$ | 30.56 |
| Conduit | | | | | \$ | 0.58 | 400 | \$ | 231.92 |
| Overall Cost | | | | | | | | \$ | 3,805,409.70 |