## **Composite Technology for Hydrogen Pipelines**



#### Barton Smith, Barbara Frame, Lawrence Anovitz

Oak Ridge National Laboratory

Annual Merit Review Arlington, Virginia May 19, 2009

Project ID #: PDP\_24\_Smith

This presentation does not contain any proprietary, confidential, or otherwise restricted information.



## **Overview**

#### Timeline

- Start: Jan 2005
- Finish: Project continuation & direction determined annually by DOE

#### Budget

- Total project funding – DOE: \$1.65M
- Funding received in FY 08

   \$600k
   \$600k
- Funding for FY 09



2 Managed by UT-Battelle for the Department of Energy

#### **Barriers**

- D. High Capital Cost and Hydrogen Embrittlement of pipelines
- Technical Targets on next slide

**Partners & Collaborators** 

- Fiberspar, PolyFlow
- Arkema, Ticona, Fluoro-Seal
- SRNL
- Pipeline Working Group



## **Overview**

### Technical Targets

Category	2005 Status	2012	2017	
Pipelines: Transmission				
Total Capital Investment (16-in pipeline, \$/mile)	\$720k	\$600k	\$490k	
Pipelines: Distribution				
Total Capital Investment (2-inch pipeline, \$/mile)	\$320k	\$270k	\$190k	
Pipelines: Transmission and Distribution				
Reliability/Integrity (including 3rd-party damage issues)	Acceptable for current service		Acceptable for H <sub>2</sub> as a major energy carrier	
H <sub>2</sub> Leakage *	Undefined	TBD	< 0.5%	

\* Leakage targets are being reviewed by the Delivery Tech Team




## **Project Milestones**

Month-Year	Milestone or Go/No-Go Decision
Sep 2008	Milestone: Survey of existing modifications and treatments available for reducing permeability in liner materials completed and reported (completed) Milestone: Recommendations for sensor integration, manufacturing and joining technologies completed and reported (50% complete)
May 2009	Milestone: Hydrogen compatibility evaluations of composite pipeline materials and construction completed (60% complete).



## **Technical Accomplishments-Initial Compatibility Testing Completed**

- Pipeline materials compatibility testing
  - Hydrogen compatibility testing following eightmonth accelerated-aging protocol showed no quantifiable materials degradation
  - Hydrogen leakage measurements in Fiberspar pipeline yielded smaller than predicted leak rates (<0.02% per day); Leakage measurements on PolyFlow FRP pipeline are in progress
  - Fiberspar FRP pipeline specimen passed blowdown testing with hydrogen



H<sub>2</sub> exposure station at SRNL



Pipeline test specimens





Leakage measurement at ORNL



## **Technical Accomplishments-Evaluation** of Joining Technologies is Progressing

- Joining and sensor technologies
  - Hydrogen leakage through Fiberspar LinePipe™ connectors is very low, <3x10<sup>-6</sup> mol/s
  - Collaborative effort underway with SRNL to assess joint loading, pipeline flexure, and pressure/temperature cycling on hydrogen leakage for both Fiberspar and PolyFlow connectors



FiberSpar connector with compressive o-ring seals



PolyFlow swaged connector



## **Completed H<sub>2</sub> compatibility screening of Fiberspar pipeline and materials**

- Accelerated aging procedure used to screen for long-term effects of hydrogen exposure on composite pipeline under normal-usage conditions
- Completed post-treatment tests of Fiberspar pipeline and constituent materials
  - Immersion in 1000 psi H<sub>2</sub>
  - Accelerated aging at 60°C for 8 months (equivalent to 5+ years at RT)
  - No deleterious effects due to H<sub>2</sub> noted in qualification testing of pipelines or tensile and DMA testing of polymer and composite matrix resin specimens




4-pt bending test specimen



Compression test specimen



SRNL H<sub>2</sub> exposure station



Liner test specimen



Glass filament specimen

## Hydrogen blowdown testing of composite pipeline

- Guidance: API 15S Qualification of Spoolable Reinforced Plastic Line Pipe, Appendix D
  - Specimen filled with hydrogen\* to pressure rating, specimen heated to temperature rating, these conditions held until pipeline structure is saturated with gas
  - Following hold period, specimen depressurize at a rate greater than 1000 psi/min
  - Following blowdown, specimen liner was examined and no visual evidences of liner blistering or collapse




3-ft pipeline specimen being instrumented for blowdown testing



\*API 15S specifies the use of supercritical CO<sub>2</sub> for blowdown testing

## Blowdown de-pressurization rate was 3X specified minimum rate


HYDROGEN BLOWDOWN TEST IN FIBERSPAR LP 4-1/2 1,500(E)



for the Department of Energy

### **Post-blowdown leakage rate was** identical to pre-blowdown rate


FIBERSPAR PIPELINE LEAKAGE MEASUREMENT Nominal 1500 psia Pressurization Moles of Hydrogen Gas in 3-ft Pipeline Specimen



for the Department of Energy

## Actual H<sub>2</sub> leakage rate is nearly 50X below predicted rate

FIBERSPAR PIPELINE LEAKAGE MEASUREMENT Nominal 1500 psi Pressurization Moles of Hydrogen Gas in 9-ft Pipeline Specimen



## Summary of H<sub>2</sub> leakage rate measurements for Fiberspar LinePipe<sup>™</sup>

Start Date	Specimen	Nominal Pressure	Leakage Rate (mol/h)
5/15/08	3-ft pre-blowdown	1500 psi	-4.4x10 <sup>-4</sup>
5/22/08	3-ft post-blowdown	1500	-4.4x10 <sup>-4</sup>
6/3/08	3-ft post-blowdown	500	(+7.6x10 <sup>-5</sup> )
3/26/08	6-ft	1500	-5.5x10 <sup>-4</sup>
4/7/08	6-ft	500	(+3x10 <sup>-4</sup> )
8/25/08	9-ft	1500	-5.5x10 <sup>-4</sup>

mal Laboratory

# Summary of H<sub>2</sub> leakage rate measurements to date

Specimen Length	Nominal Pressure (psig)	Measured Leakage Rate (mol/h)	Predicted Leakage Rate (mol/h)
3-ft	1500	-4.4x10 <sup>-4</sup>	-8.2x10 <sup>-3</sup>
6-ft	1500	-5.5x10 <sup>-4</sup>	-1.6x10 <sup>-2</sup>
9-ft	1500	-5.5x10 <sup>-4</sup>	-2.5x10 <sup>-2</sup>

In most extensive test to-date, hydrogen lost due to permeation and leakage through end cap seals was less than 0.02% per day. The rate is 45 times below the predicted value for HDPE (PE-3408) liner.



# Summary of H<sub>2</sub> leakage rate measurements to date

- Loss due to leakage is much lower than expected (and might be good enough to meet leakage target)
- Reinforcement layer might be providing some gas barrier benefit but probably can't account for full extent of discrepancy between predicted and measured values
- Rapid decompression of pipeline is probably not going to be a failure mechanism for liner
- Joints with elastomeric seals have worked well (so far)




# Future directions for H<sub>2</sub> leakage rate measurements in Fiberspar FRP pipeline

- Subject specimens to 4-pt bend testing to reveal the extent of how microcracking increases permeation and leakage
- Measure pressure as a function of depth in wall or within composite layers




### Hoop strain in Fiberspar FRP pipeline during leakage measurements




for the Department of Energy

### **Axial strain in Fiberspar FRP pipeline during leakage measurements**



## H<sub>2</sub> leakage rate measurements in PolyFlow Thermoflex<sup>®</sup> Reinforced Pipe

- Liner: Coextruded PPS and PA-6
- Reinforcement: aramid fiber rovings braided on liner, laid over four longitudinal rovings
- Burst strength determined by braid angle, not by number of plies
- PP jacket with damage indicating colorant
- Couplings with swaged metal seals
- Leakage rate measurements in progress





## **Future Work**

- FY 2009
  - Report test results from 8-month accelerated aging and hydrogen exposure of pipeline and material specimens
  - Continue measurements of liner materials, including measurements of surface fluorination samples, using new diffusion and permeation measurement apparatus for polymers with additional capabilities
  - Begin assessment of possible hydrogen-induced cracking in the reinforcement layers during cyclical strain, perform long-term stress rupture tests, perform high-pressure cyclical fatigue tests, assess joint sealing under cyclic loading
  - Collaborate on development of codes & standards for hydrogen-service FRP pipelines
- FY 2010
  - Coordinate initial field test of FRP pipeline for hydrogen service, providing springboard for commercially viable demonstration project



## **Project Summary**

<b>Relevance:</b>	Need viable alternative to metallic pipelines to
	achieve cost and performance targets for
	hydrogen transmission and distribution

- Approach: Investigate applicability of commercially available FRP polymer pipelines and develop path forward for hydrogen delivery
- Progress: Cost scenario shows composite pipelines can meet DOE 2012 goals and are close to 2017 goals; hydrogen compatibility of pipeline materials is acceptable; pipeline leakage rates are lower than predicted

#### **Collaborations:** Pipeline and polymer industries, National Lab

Future:Codes & standards; prototype FRP pipelinesystem for H2 delivery; demonstration project

