Extended durability testing of an external fuel processor for SOFC

Mark A. Perna Rolls-Royce Fuel Cell Systems (US) Inc. (RRFCS) June 8, 2010

DOE Project Officer: Jesse J. Adams

Project ID: FC072

This information is given in good faith based upon the latest information available to Rolls-Royce Fuel Cell Systems (US) Inc. No warranty or representation is given concerning such information, which must not be taken as establishing any contractual or other commitment binding upon Rolls-Royce Fuel Cell Systems (US) Inc. or any of its subsidiary or associated companies.

This document does not contain any Export Controlled Data.

Acknowledgement: "This material is based upon work supported by the U.S. Department of Energy under Award Number DE-FG36-08GO88113."

Disclaimer: "This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, as assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product, or process disclosed, or represents that its us would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring the United States Government or any agency thereof. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government of any agency thereof.

This information is given in good faith based upon the latest information available to Rolls-Royce Fuel Cell Systems (US) Inc. No warranty or representation is given concerning such information, which must not be taken as establishing any contractual or other commitment binding upon Rolls-Royce Fuel Cell Systems (US) Inc. or any of its subsidiary or associated companies.

This document does not contain any Export Controlled Data.

Overview

Timeline

- Project start: 01/01/2009
- Project end: 12/31/2011
- Percent complete: 31%

Budget

- Project funding total \$1,968,000
 - DOE share = \$984,000
 - RRFCS (US) Inc. = \$984,000
- Funding received in FY08 \$984K
- Funding in FY09 \$0.0K
- Funding in FY10 \$0.0K

Barriers

Fuel Processor

- Durability
- Performance
- Start-up and Shutdown time
- Transient operation

Partners

- RRFCS project lead
- Ohio Department of Development / Stark State College of Technology
 - Funding for Outdoor Test Facility
 - Student Interns

Relevance Stationary power generation with fuel cells

Rolls-Royce Fuel Cell Systems (US) Inc. (RRFCS) believes its 1 MWe Solid-Oxide Fuel Cell (SOFC) power plant concept is best suited for stationary power generation applications. With its high electrical efficiency (~60%), negligible air emissions, and minimal noise profile, the concept is highly suitable for connection to local distribution networks in small, secure urban areas. The applications of interest include hospitals, universities, shopping malls, factory units, etc.

The 1 MWe SOFC power plant will be configured initially to use pipeline natural gas. Future development may target coal synthesis gas, liquid hydrocarbon fuels and alternative fuels such as biogas.

Relevance

RRFCS' SOFC power plant concept through its high efficiency, negligible air emissions and potential fuel flexibility directly supports the DOE Hydrogen Program's mission statement "to reduce petroleum use, greenhouse gas emissions, and air pollution and to contribute to a more diverse and efficient energy infrastructure by enabling the widespread commercialization of hydrogen and fuel cell technologies."

RRFCS' SOFC power plant concept for stationary power supports the DOE Hydrogen Program's goal to advance fuel cell technologies "...through research, development, and validation efforts – to be competitive with current technologies in cost and performance, and to reduce the institutional and market barriers to their commercialization."

Relevance **Technical barriers**

This project addresses technical barriers A - durability, C - performance, and G - start-up and shut-down time and energy / transient operation from the Fuel Cells section of the Hydrogen, Fuel Cells and Infrastructure Technologies Program (HFCIT) Multi-Year Research, Development and Demonstration (RD&D) Plan.

These barriers will be addressed as they relate to the external fuel processor in RRFCS' 1 MWe SOFC power plant concept.

Relevance Specific targets and milestones

This project addresses milestones 59 in the Fuel Cells section of the Hydrogen, Fuel Cells and Infrastructure Technologies Program (HFCIT) Multi-Year Research, Development and Demonstration (RD&D) Plan.

Milestone 59 is to "evaluate fuel processing subsystem performance for distributed generation against system targets for 2011." These targets will be addressed as they relate to durability, performance, and transient response.

Relevance

External fuel processor for SOFC

The external fuel processor for the RRFCS 1 MWe SOFC power plant concept uses only air and pipeline natural gas to provide all required gas streams for:

- Start-up & shutdown nonflammable reducing gas
- System heat-up and part-load operation synthesis gas
- Normal operation desulfurized natural gas

The external fuel processor eliminates the need for onsite storage of high-pressure gas cylinders to supply hydrogen and nitrogen

Relevance Overall Objectives

- Conduct long-term tests in relevant environments for the three fuel processor subsystems that support operation of the 1 MWe SOFC power plant. The subsystems include:
 - Synthesis-gas subsystem
 - Start-gas subsystem
 - Desulfurizer subsystem
- Determine long-term performance of key components such as catalysts, sorbents, heat exchangers, control valves, reactors, piping, and insulation
- Evaluate the impact of ambient temperatures (hot and cold environment) on performance and component reliability
- Determine system response for transient operation

Relevance Objectives

The project objectives from June 2009 through May 2010 included:

- Obtain DOE approval for the project's hydrogen safety plan
- Complete synthesis-gas subsystem durability testing
- Install desulfurizer and start-gas subsystems in outdoor test facility
- Complete shakedown and commissioning of desulfurizer and start-gas subsystems

Approach

Operate fuel processor subsystems on pipeline natural gas for extended periods

Conduct subsystem tests in <u>relevant environments</u>

- •Synthesis-gas subsystem up to 1,200 hours in warm environment
- •Start-gas subsystem up to 200 hours in outdoor environment (hot / cold)
- •Desulfurizer subsystem for 8,000 hours in an outdoor environment (hot / cold)

Perform post-test inspections and analyses

- Physical and chemical analyses of catalysts, sorbents, piping, reactors, and insulation
- Functional checks of control valves, heaters, heat exchangers, control system sensors and safety system sensors
- •Identify any deposits and signs of wear, damage, corrosion or erosion

Approach Planned milestones

No.	Description	Planned	
1	Start Preparation of Synthesis-gas Subsystem	January 2009	
2	Begin Synthesis-gas Subsystem Durability Testing	April 2009	
3	Start Preparation of Desulfurizer Subsystem	July 2009	
4	Complete Synthesis-gas Subsystem Durability Test	September 2009	
5	Complete 1,000 hours Operation of Desulfurizer	September 2010	
6	Start Preparation of Start-gas Subsystem	July 2009	
7	Begin Start-gas Subsystem Durability Testing	September 2010	
8	Complete Desulfurizer Subsystem Test	October 2011	
9	Complete Start-gas Subsystem Test	October 2011	
10	Complete Final Report	December 2011	

Synthesis-gas subsystem generates a hydrogenrich gas for SOFC heat-up and low-load operation

- Synthesis gas (H₂ and CO) generated from pipeline natural gas and compressed air
- The synthesis-gas subsystem uses:
 - Catalytic, partial oxidation reactor
 - Automatic control system for unattended operation

Synthesis-gas subsystem test plan

Operate Synthesis-gas subsystem for up to 1,200 hours

- Determine synthesis gas composition as a function of load (10%, 50% and 100% of design flow)
- Determine any impact of operating time on gas composition (hydrogen, carbon monoxide and methane)
 - Target performance less than 10% reduction in H₂ content over catalyst life

Perform 10 start-up cycles

Determine any impact of operating time on start-up time and light-off

Post-test examination

- Disassemble Synthesis-gas reactor
 - Determine catalyst surface area, pore volume, carbon content, sulfur content and loss of precious metals
 - Examine reactor vessel, inlet and outlet piping, and internal components (use scanning electron microscope to examine samples when needed)
 - Inspect insulation and internal components

Approach

Start-gas subsystem generates a nonflammable reducing gas that is used for SOFC start-up and shutdown

- Start-gas is to be generated from pipeline natural gas and an oxygen-depleted air stream
- The start-gas subsystem uses:
 - Low-oxygen content oxidant stream generator
 - Catalytic reactor to generate hydrogen and carbon monoxide
 - Air-cooled heat exchanger to cool product gas
 - Automatic control system for unattended operation

Approach Start-gas subsystem test plan

Operate Start-gas subsystem for up to 200 hours

- Determine gas composition at full-load conditions
- Determine impact of operating time on gas composition (hydrogen, carbon monoxide, and methane)
 - Target performance less than 20% variability in flammables content

Perform 24 start-up cycles

Determine impact of operating time on start-up time and light-off temperature

Post-test examination

Disassemble Start-gas reactor

- Determine catalyst surface area, pore volume, carbon content, sulfur content and any change in precious metals loading
- Examine reactor vessel, heat exchanger and piping
 - (use scanning electron microscope to examine samples when needed)
- Inspect insulation and internal components

Approach Desulfurizer subsystem generates highpressure desulfurized natural gas

- The SOFC requires high pressure (10 Bara) desulfurized natural gas (< 100 ppb)
- The desulfurizer subsystem uses:
 - Pipeline natural gas (2 to 10 ppmv sulfur) and compressed air as reactant
 - Catalytic reactor for oxy-desulfurization with high-capacity sulfur sorbent
 - Automatic control system for unattended operation

Approach

Desulfurizer subsystem test plan

Operate desulfurizer subsystem for up to 8,000 hours

- Determine sulfur content in product gas at part-load and full-load
- Determine impact of operating time on product gas composition (sulfur, methane, ethane, propane, butane, pentane and carbon dioxide)
- Target performance
 - Less than 100 ppb sulfur in product desulfurized natural gas
 - Desulfurized natural gas retains >98% of its original calorific value

Post-test examination

- Disassemble reactor, sorbent vessel and start-up burner
 - Determine catalyst surface area, pore volume, carbon content, sulfur content and any change in precious metals loading
 - Determine sorbent carbon content and sulfur contents (SO₂/SO₃)
 - Examine reactor, vessels, start-up equipment, heat exchanger, and piping (use scanning electron microscope to examine samples when needed)
 - Inspect insulation and internal components

Technical accomplishments and progress

- Hydrogen safety plan issued and approved by DOE's safety review panel
- Synthesis-gas subsystem installed, commissioned, and tested
- Fabrication of outdoor test facility completed
- Start-gas subsystem installed in outdoor test facility
 - Control software commissioning underway
 - Mechanical commissioning underway

• Desulfurizer subsystem installed in outdoor test facility

- Control software written and being commissioned
- Mechanical commissioning underway

This presentation does not contain any proprietary, confidential, or otherwise restricted information

19

Technical accomplishments and progress Synthesis-gas reactor installed in test enclosure



This presentation does not contain any proprietary, confidential, or otherwise restricted information

DE-FG36-08GO88113

Rolls-Royce Fuel Cell Systems

20

Technical accomplishments and progress 21 **Synthesis-gas subsystem durability testing results** Synthesis gas hydrogen



- Hydrogen in product gas decreased with time-on-stream
 21% decrease in hydrogen concentration at 100% load after 1,000 hours of operation
 7% decrease in hydrogen concentration at 15% load after 1,000 hours of operation
- Observed decreases in hydrogen not expected to be an issue

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Technical accomplishments and progress 22 Synthesis-gas subsystem durability testing results

Synthesis gas carbon monoxide



- Carbon monoxide in product gas decreased with time-on-stream 11% decrease in CO concentration at 100% load after 1,000 hours of operation 3% decrease in CO concentration at 15% load after 1,000 hours of operation
- Observed decrease in carbon monoxide not expect to be an issue

Technical accomplishments and progress 23 Synthesis-gas subsystem durability testing results





Hrs of Operation

- Methane in product gas increased with time-on-stream At 100% load, methane more than doubled (after 1,000 hours of operation) At 15% load methane increased ~ 40% (after 1,000 hours of operation)
- Observed increase in methane not expected to be an issue

Technical accomplishments and progress 24 **Synthesis-gas subsystem durability testing results**



- Light-off temperature was 350C
- Approximate start-up time was two minutes to target hydrogen level
- Hydrogen generation followed catalyst outlet temperature

Technical accomplishments and progress 25 Start-gas subsystem hardware before installation in outdoor test facility



This presentation does not contain any proprietary, confidential, or otherwise restricted information

DE-FG36-08GO88113

Technical accomplishments and progress **1 MWe Desulfurizer subsystem hardware before installation in outdoor test facility**



This presentation does not contain any proprietary, confidential, or otherwise restricted information

DE-FG36-08GO88113

Technical accomplishments and progress

Installation of Desulfurizer and Start-gas subsystems in outdoor test facility



This presentation does not contain any proprietary, confidential, or otherwise restricted information

DE-FG36-08GO88113

Technical accomplishments and progress

Milestones

No.	Description	Planned	Actual	Status
1	Start Preparation of Synthesis-gas Subsystem	January 2009	January 2009	completed
2	Begin Synthesis-gas Subsystem Durability Testing	April 2009	September 2009	completed
3	Start Preparation of Desulfurizer Subsystem	July 2009	December 2009	completed
4	Complete Synthesis-gas Subsystem Durability Test	September 2009	April 2010	completed
5	Complete 1,000 hours Operation of Desulfurizer	September 2010		on schedule
6	Start Preparation of Start-gas Subsystem	July 2009	December 2009	completed
7	Begin Start-gas Subsystem Durability Testing	September 2010		on schedule
8	Complete Desulfurizer Subsystem Test	October 2011		on schedule
9	Complete Start-gas Subsystem Test	October 2011		on schedule
10	Complete Final Report	December 2011		on schedule

Collaborations

- RRFCS is the project lead. Significant collaboration between RRFCS and the Ohio Department of Development (ODOD) was required to enable this project to go forward.
- The Ohio Department of Development provided funding (\$3 million) through Ohio's Third Frontier to expand the Fuel Cell Prototyping Center located on the Stark State College of Technology (SSCT) campus. The expansion included construction of:
 - Outdoor and indoor test facilities for use by RRFCS
 - SSCT's Fuel Cell Center (laboratory space for fuel cell education)
- SSCT has associate degree programs in electrical engineering technology and mechanical engineering technology with a fuel cell option. RRFCS has five graduates of these programs as either interns or as permanent employees to support this and other fuel cell projects.

Proposed future work

<u>2010</u>

- Perform post-test inspection and analyses of synthesis-gas subsystem (FY10 Q3)
- Complete commissioning of Start-gas and Desulfurizer subsystems (FY10 Q2)
- Begin durability testing of Start-gas and Desulfurizer subsystems (FY10 Q3)

<u>2011</u>

- Complete durability testing of Start-gas and Desulfurizer subsystems (FY11 Q3)
- Perform post-test inspections of Start-gas and Desulfurizer subsystems (FY11 Q4)
- Issue final report for project (FY11 Q4)

Summary

- An approach was developed for testing durability and performance of an external fuel processor for a SOFC
- Durability testing has been completed on the Synthesis-gas subsystem
- The Desulfurizer and Start-gas subsystems have been installed in the outdoor test facility. Commissioning is underway.