

# Hydrogen Delivery Sub-program - Session Introduction -

Scott Weil


2011 Annual Merit Review and Peer Evaluation Meeting

May 10, 2011

## Goals and Objectives



Develop technologies to reduce the cost of H<sub>2</sub> delivery to the point that H<sub>2</sub> is competitive with other energy carriers and fuels



- Storage at production site
- Liquefier (gas to liquid)
- Carrier production/regeneration

- Pipelines
- Trucks, rail, barges vessels
- Pipeline compressors
- City gate storage
- Geological storage
- Terminals

## Crosscutting Delivery Technology Components

Sensors & controls
Health & human safety

Codes & standards

Rights of way/permitting

Carrier transfiguration

Separation/purification

Compression/vaporization


Forecourt storage

Fuel dispensers

## **Delivery Budget**



**FY 2010 Appropriation = \$5.02M FY 2012 Request = \$6.63M** 



#### **EMPHASIS**

- Reduce pipeline delivery cost
  - Centrifugal pipeline compressor design using "off-the-shelf parts"
  - High RPM pipeline compressor design to reduce size and cost while increasing efficiency
  - Fiber reinforced polymer pipeline alternative to steel pipeline
- Increase the gas capacity of tube truck delivery
  - ▶ Large volume /high pressure vessel
  - High pressure/low temperature glass fiber wrapped vessel
- Increase the efficiency of H<sub>2</sub> liquefaction
  - Helium cycle with a novel heat exchanger configuration
  - Magnetic cooling
- Analysis of costs
  - Update HDSAM to \$2007 and evaluate technology and economies of scale cost drivers
  - Evaluate delivery pathways and key cost drivers

## Challenges



The key challenge in this sub-program is to reduce the cost of delivering  $H_2$  (including on-site compression, storage, and dispensing) to \$1/gge\*.

Delivery Element	Goal (2015/2017 Targets)*	Status**
Tube trailers	<ul> <li>Reduce capital cost to &lt; \$200,000</li> <li>Increase capacity to 1100kg</li> </ul>	<ul> <li>Capital cost: \$470,000 capital cost (250 bar carbon fiber vessel,</li> <li>Capacity: 550kg</li> <li>Cost contribution: \$0.9/kg H<sub>2</sub></li> </ul>
Liquefaction	<ul> <li>Reduce installed capital cost to \$100M</li> <li>Increase energy efficiency to 87%</li> </ul>	<ul> <li>Installed capital cost: \$200M</li> <li>System Efficiency: 76%</li> <li>Cost contribution: \$1.6/kg H<sub>2</sub></li> </ul>
Pipeline technology	• Reduce cost/mile (installed) to <\$490K	<ul> <li>Installed steel pipeline cost: \$3M/mile</li> <li>Cost contribution: \$1.7/kg H<sub>2</sub></li> <li>Compressor cost contribution: \$0.1/kg H<sub>2</sub></li> </ul>
Forecourt compression (1000 kg/day station)	<ul> <li>Reduce installed capital cost to \$187.5K for 700 bar, 1500kg/day dispensing</li> </ul>	<ul> <li>Capital cost: \$1.5M for 700 bar dispensing (cost contribution of \$2/kg H<sub>2</sub>)</li> <li>Capital cost: \$0.5M for 350 bar dispensing (cost contribution of \$0.8/kg H<sub>2</sub>)</li> </ul>
Forecourt storage (1000 kg/day station)	<ul> <li>Reduce tank cost/kg H<sub>2</sub> stored to \$300 (current \$1000)</li> </ul>	<ul> <li>Storage tank cost: \$1000/kg H<sub>2</sub> stored (\$0.4/kg H<sub>2</sub>)</li> </ul>

<sup>\*</sup>Based on FY10 MYPP targets. These are being updated this year.

<sup>\*\*</sup> High volume projections based on HDSAM (v. 3) – will be peer reviewed and publicly vetted.

## Challenges: Techno-economic



#### Capital costs are an issue for all pathways.







- Tube trailers (early market scenario)
  - Capacity
  - Capital cost
  - Regulatory issues with transportation of high-pressure vessels
- Liquid H<sub>2</sub> delivery (early and mid-term market scenarios)
  - Energy efficiency of liquefaction
  - Transfer boil off
  - Capital cost
- Pipelines (long-term market scenario)
  - Managing embrittlement (steel pipelines) to reduce lifetime cost
  - Capital and installation costs
  - Cost & durability/reliability of pipeline compressors
  - Hydrogen quality
  - Bulk storage (geologic)
- Forecourt
  - Cost/efficiency and reliability of station compressors and dispensers
  - Capital cost per kg H<sub>2</sub> stored of station storage

## **Progress: Tube Trailer Delivery**



Identified design parameters to increase trailer capacity to 800 kg and reduce capital cost to \$450/kg H<sub>2</sub> stored

#### **Prior Accomplishments**

- Met key interim program goals:
  - Successfully tested 250 bar vessel/ISO frame capable of 600 kg H<sub>2</sub> capacity
  - Achieved a projected reduction in tube trailer delivery cost of >33%
  - Identified a route to increase capacity to 1,100 kg H<sub>2</sub> and reduce trailer cost by 50% using cold compressed glass fiber vessels

#### **Recent Accomplishments**

- Completed a design trade study on carbon fiber wrapped vessels :
  - Vessel pressure can be increased an additional 100 bar (350 bar)
  - Carrying capacity can be increased an additional 33% (800 kg H<sub>2</sub>)
  - ▶ Transport cost can be reduced another 10%
- Successfully fabricated and hydroburst tested a full-scale glass fiber wrapped vessel



#### **Future Work**

- Complete design and qualification of a 350 bar tank
- Pressure and thermal cycle test full scale glass fiber wrapped vessels

Pls: Lincoln Composites and LLNL

## Progress: H<sub>2</sub> Liquefaction



## Increased Claude-cycle efficiency; Fabricated alternative H<sub>2</sub> liquefaction prototype

#### **Prior Accomplishments**

- Developed software that accounts for ortho-para LH<sub>2</sub> effects and helps identify efficiency improvements
- Completed design of a continuous catalytic heat exchanger (CHEX) – projected to improve HX performance
- Designed and fabricated 5 of 8 sub-systems for active magnetic regenerative refrigerator (AMRR)



#### **Recent Accomplishments**

- Improved ortho-para conversion performance with a catalyst – reduces total power required for liquefaction by 2.4%
- Fabricated the CHEX for testing
- Fabricated and integrated all sub-systems into a prototype AMRR device – in testing

#### **Future Work**

- Complete testing of the CHEX device
- Incorporate lessons learned from AMRR prototype testing into the design of a final phase rotary device
- Fabricate and test a demonstration-scale rotary AMRR device

Pls: Praxair, GEECO, and Heracles Energy Corp.


## **Progress: Pipeline Materials**



#### Projected reduction in installed pipeline costs of 15%

#### **Prior Accomplishments**

- Identified steel microstructures responsible for H<sub>2</sub> embrittlement resistance
- Determined that the level of H<sub>2</sub> permeation through fiber reinforced polymer (FRP) pipeline materials will meet DOE targets and FRP burst strength
- Demonstrated no degradation in FRP after 8mo of accelerated aging (equivalent to 5yrs at room temperature)



#### **Recent Accomplishments**

- Developed models to simulate the effects of H<sub>2</sub> on the mechanical properties of pipeline steels
- Demonstrated a 3x design margin for FRP through flaw tolerance testing
- Projected reduction in installed pipeline cost of 15%

#### **Future Work**

- Establish protocols with codes committees to develop performance qualification test methodology for FRP
- Initiate FRP performance testing

PIs: U. Illinois, SECAT, SNL, ORNL, SRNL

## **Progress: Pipeline Compression**




Projected reduction in pipeline compressor capital cost of 20% and O/M costs of 30% based on new designs


#### **Prior Accomplishments**

- Completed an initial design study of a pipeline compressor (Concepts NREC) concept that utilizes off-the-shelf technology and is projected to meet the DOE FY2017 targets
- Completed an initial design of a high speed pipeline compressor (MITI) that also is projected to meet the DOE FY 2017 targets

#### **Recent Accomplishments**

- Completed detailed design and thermomechanical analyses of the Concepts NREC compressor concept
- Completed detailed design and thermomechanical analyses of a single-stage MITI prototype compressor
- Fabricated key components (e.g. rotor) for prototypes of each compressor technology





#### **Future Work**

- Conduct component testing and post-test analysis
- Fabricate compressor prototypes for performance testing


PIs: MITI, Concepts NREC, ANL

## Progress: Analysis/Forecourt CSD



## Station costs now dominate pathway delivery costs.

#### **Example: Pipeline delivery pathway**



<sup>\*</sup> Cost projections based on 15% market penetration

## **Progress: Analysis/Forecourt CSD**



#### Identified key barriers to delivery and forecourt cost reductions

#### **Prior Accomplishments**

- Completed fuel station footprint and wind-to-LH<sub>2</sub> analyses and added 700 bar gas and cryocompressed delivery options to models
- Demonstrated electrochemical hydrogen compressor (EHC)
  - Achieved a 300:1 compression ratio in a single stage design
  - Passed 500 hr testing at that time
  - Project a 5x reduction in energy consumption and improved device reliability relative to current technology

PIs: FuelCell Energy, ORNL, LLNL, ANL, NREL, PNNL

#### **Recent Accomplishments**

- Published pipeline cost analysis study
- Updated HDSAM/H2A, including \$2007
- Identified a key cost barrier: compression, storage, and dispensing (CSD) at the forecourt
- Achieved 420 bar in a 2-stage EHC design, with the potential to reach 840 bar. Doubled the rate of compression


#### **Future Work**

- Identify technology and pathway options to reduce refueling station costs
- Design test facility to test 2-stage, 840 bar EHC
- Detailed design of reinforced concrete steel lined storage vessel



#### Key Milestones & Future Plans

- Update HDSAM (to 2007 dollars) publication in progress
- Verify tube trailer vessel capacity to 350 bar
- Complete prototype centrifugal compressor systems in preparation for testing
- Pipeline working group meeting (9/11)
- Update Delivery technology/cost targets and Multi-Year Plan in progress
- Establish the feasibility and define the cost for geologic hydrogen storage
- Complete LH<sub>2</sub> pump installation at LLNL in preparation for refueling and cryo-compressed vessel tests



## For More Information



#### **H<sub>2</sub> Delivery Sub-Program**

DOE Headquarters:

Sara Dillich

*H*<sub>2</sub> *Production & Delivery Team Leader* 202-586-7925

sara.dillich@ee.doe.gov

**Scott Weil** 

*H*<sub>2</sub> *Delivery Infrastructure, Detail from PNNL* 202-586-1758

kenneth.weil@ee.doe.gov

**Monterey Gardiner** 

 $H_2$  Delivery Infrastructure, Mansfield Fellow – on assignment

202-347-1994

Mrgardiner.os@gmail.com

Golden Field Office:

**Paul Bakke** 

303-275-4916

paul.bakke@go.doe.gov

**Technical Support:** 

**Kristine Babick** 

Program Support, Energetics

202-586-1738

kristine.babick@ee.doe.gov

## **Session Instructions**



- This is a review, not a conference.
- Presentations will begin precisely at the scheduled times.
- Talks will be 20 minutes and Q&A 10 minutes.
- Reviewers have priority for questions over the general audience.
- Reviewers should be seated in front of the room for convenient access by the microphone attendants during the Q&A.
- Please mute all cell phones, BlackBerries, etc.
- Photography and audio and video recording are not permitted.

## **Reviewer Reminders**



- Deadline for final review form submittal is May 20<sup>th</sup> at 5:00 pm.
- ORISE personnel are available on-site for assistance. A reviewer-ready room is set-up in The Rosslyn Room (on the lobby level) and will be open Tuesday –Thursday from 7:30 am to 6:00 pm and Friday from 7:30 am to 2:00 pm.
- Reviewers are invited to a brief feedback session
   at 3:45pm on Thursday, in this room.

## **EERE Fellowship Program**



- Fuel Cell Technologies Program Opportunities Available
  - Conduct applied research at universities, national laboratories, and other research facilities
  - Up to five positions are available in the areas of hydrogen production, hydrogen delivery, hydrogen

storage, and fuel cells

- Applications are due June 30, 2011
- Winners will be announced mid-August
- Fellowships will begin in mid-November 2011

www.eere.energy.gov/education/postdoctoral\_fellowships/



## Participating Organizations/Collaborators



#### Analysis

- ANL
- NREL
- ▶ PNNL

#### Forecourt Compression/Storage

- AC Transit
- Fuel Cell Energy
- NASA
- ▶ ORNL

#### H<sub>2</sub> Liquefaction & Delivery

- Gas Equipment Engineering Corporation
- Linde Corporation
- **LLNL**
- Praxair
- Promethius Energy

#### Pipeline & Pipeline Compression

- ANL
- Concepts NREC
- DOT
- ▶ I<sup>2</sup>CNER
- ▶ MITI
- NASA
- ▶ NIST
- ▶ ORNL
- Secat
- SNL
- ▶ SRNL
- University of Illinois

#### Carriers

- Air Products
- ▶ PNNL

#### Sub-program Review

- ▶ BP
- Chevron
- Exxon-Mobil