This presentation does not contain any proprietary, confidential, or otherwise restricted information





High-Capacity, High Pressure Electrolysis System with Renewable Power Sources

Paul Dunn and Dave Mauterer, Avalence LLC DOE Merit Review, 11 May 2011

Project # PD029



DOE Program Overview & Barriers Addressed

Timeline

Start Date: Jun 2008 End Date: Sep 2011 Percent Complete: 55%

Budget

Project Funds: \$2.40M DOE: \$1.92M Contractor: \$0.48M FY 08 Funds: \$393K Spent FY 09 Funds: \$487K Spent FY 10 Funds: \$300K Allocated \$105K Spent FY11 Funds: \$375K Allocated FY12 Funds: \$365K Allocated

Barriers Addressed

Capital Cost System Efficiency Renewable Power Integration

Partners Avalence: Lead Gas Equipment: Sister-company HyperComp: Composite Wrapping

-2-



DEVELOPMENT PROGRAM MILESTONES

| Project Milestones | × * * |
|--|-----------------|
| Description | Status |
| Determine a Manifolding and Sealing Arrangement for Nested Cell | Complete |
| 1) H_2 and O_2 Gas Separation | 1 7/3 2 |
| 2) Electrical Connection to Electrodes | |
| 3) Electrolyte Replenishment | |
| Determine Containment Penetration Size and Design | Complete |
| 1) Compatible with Composite Wrapped Vessel Constraints, | |
| 2) Support Cell Electrode Current Magnitudes (>1000 amp) | |
| 3) H_2 and O_2 Gas Off-Take | |
| 4) Electrolyte Replenishment | |
| Design a Functional Shape of Outer Metal Jacket For Dual Purpose: | Complete |
| Outer Electrode's Inner Surface | |
| Vessel Liner that is the Foundation for Composite Wrap | |
| Demonstrate the Performance of the Nested Cell Core so that Accurate Projections of | In Process |
| Energy Use can Be Integrated into the Cost Model | |
| Demonstrate the Ability to Implement a Composite Fiber Outer Wrap Over the Nested Cell | In Process |
| Core | |
| Produce a Pilot Plant Design For Use as a Basis for a Sound Economic Analysis of Plant | In Process |
| Fabrication and Operating Cost | |
| Demonstrate the Operation and Efficiency of the Pilot Plant | Not Yet Started |
| Laboratory Testing at Avalence | |
| Field Testing at NREL | |
| Have a Site Ready to Accept the Completed Plant for Commercial Operation | Not Yet Started |
| 100 kW of Renewable Power in Place | |
| Sale or Use of the Plant Products Defined | |



What's Different About Avālence?

- Company formed as a spin-off of two established entities
 - Gas Equipment Engineering Corp.
 - Electric Heating Equipment Company
- Avālence Hydrofillers operate via Alkaline Electrolysis (KOH Electrolyte)
- Avalence Hydrofillers operate at a pressure of not less than 2,000 psig – and in some units at much higher pressure
 - Reduced or <u>Zero</u> Compression Power
 - Vastly Reduced Dryer Power / Loss
- Avalence Hydrofiller <u>cells</u> are designed for continuous operation – units in field with 40,000+ hours





Goals (subset), Design Approach, and Challenges

- Achieving at Least a 15 X Increase in the Production Rate of a Single Cell
- Demonstrate the High Pressure Cell Composite Wrap Which Enables Significant Weight Reduction
- Maintain Cylindrical Pressure Boundary Configuration
- Increase the Diameter By Using a Composite Outer Wrap
- Place Multiple Electrode and Membrane Pairings Inside a Single Cell Body

- Electrodes Act as Two Sided Unipolar Electrodes
- Large Diameter Membrane Formation
- Membrane to Manifold Sealing
- Fluid and Power Penetrations
- Composite Wrapping "Heavy" Cylinder
- Process Control of a Multiple, High-Capacity Cell Array
- Long-Term Operation at 6500 psi (O2 Side Purity)
- Low/No Leakage Electrical Isolation Hoses at 6500 psi



Last Year...

Around

- We got it to work (6,500 psig), but it didn't meet company (or CE / TUV) safety standards
- And, we had efficiency loss

AVALENCE

Significant Project Accomplishments

- 1) Identified and Tested Formable Sheet Membrane Material
- 2) Successfully Demonstrated Membrane **Tube Forming and Seam Joining**
- Identified Vendor and Ordered 6500 psi **Capable Electrical Isolation Hoses**
- Completed Design of Single Cell Test Article and Test Apparatus
- 5) Demonstrated 6500 psi Production on **Small Capacity Cells**



Demonstrated 6500 psi Operation

- Legacy cells used for testing
- Multiple ٠ membrane materials tested
- 80 mil thick membrane performed "OK" (lost efficiency)
- Electrolyte . requires weekly "Decompression" to maintain purity
- "Not ideal" . (NO SAFETY MARGIN)





Increasing 80 mil 67 kWh/ka Thickness Decreased Efficiency 40 mil 62 kWh/kg



6,500 psig!! (Why It's Hard...)

- Electrochemistry still works, but...
 - Bubbles are very small (almost invisible)
 - Velocity of bubbles is low (masking)
 - Since velocity is lower, dwell time in cells increases
 - This by itself can impact purity...
 - More time to react with any electrolyte contaminants
 - Greater time for any side electrolysis reactions (hoses) to accumulate impurity
 - Since diffusion is either steady or increasing with pressure, the additional dwell time amplifies any impurity as a result of diffusion
 - And all other leak paths, which seemed to be trivial before, become <u>monsters</u>
 - NPT threads (we had to remove them from the cell design)
 - Dielectric Hoses (we had multiple attempts before success)
 - Internal cell seals (we have redesigned head on legacy cells, and used those design concepts on large cell)



6,500 psig (Why It's Worth It...)

- 5,000 psig is a standard pressure for industrial vehicles
 - Buses
 - Forklifts
 - Other logistics support vehicles
- Compressor power can be eliminated (replaced by water pumping power)
 - The compressor (multistage especially) is a major source of complexity, unreliability, and maintenance
 - For those few applications with extreme pressures (10,000-20,000 psig), the compressor will be one stage only (diaphragm)
- Since H2 is saturated in water at electrolysis pressure, higher electrolysis pressure means vastly reduced dryer power
 - In some cases, no additional drying is required



This Year...

- Tested nested components of large cell with recirculation (but not all together)
 - Done
- Build two large cells (in process)
 - Stainless version (~1,000 psig)
 - Composite overwrap version (2,800 to 6,500 psig)
 - 6,500 psig with external axial support
- Test large cells (in process)
- Build pilot plant using array of large cells (planned)
 - With axial support structure







ALENCEILC Evolution from Legacy Approach





New Cell Results

- 10 cell test string run with:
 - Partial Nested Electrode set
 - Anolyte and Catholyte circulation
 - More efficient membrane
 - New head design (better sealing)
- Improved polarization (even when cold) (even on a current density basis)
 - Massively reduced masking
- Purity at 2,500 psig 99.7%!!! (before catalyst / cleanup)
 - Vs. 97.0% with Legacy Design
 - We now have safety margin ++
- Endurance testing still underway, probably 1,000 hours at this point
 - We believe level control and thermal management will be issues (in nested cell), but are resolvable







Nested System – Next Steps

- Fully loaded nested test cell (with 1 meter membranes) will be tested at up to 1,000 psig, then composite wrapped and tested at 2,000 psig, then full pressure (with modified closure)
 - Metalic components will take 1,400 psig (hoop stress) or 2,800 psig (axial stress)
 - Composites and tie rods get us to 6,500+ psig
- Pilot Plant will demonstrate module(s) of nested cell
 - 2x2 is the likely configuration (best for 6,500 psig)
 - Larger modules, 3x3, 5x5 possible, but result in VERY high currents





Avālence Hydrofiller ISO Series

- Avalence will continue to produce variants of the Hydrofillers (the core of the nested cell)
 - HF-15 to HF-175
 - 0.75 to 10.0 kg H2/day per electrolyzer
 - Small footprint, suitable for laboratory or outdoor environment
- Avālence will offer larger, lower cost (per kg), higher performance *Hydrofillers* in ISO Container sizes (variants of the nested cell)
 - 8'x 8.5 / 9.5' x 20', 30', 40', or 53' Standard Hi Cube
 ISO Van sizes
 - Depending on pressure, we expect these units to cover the range of 30-120 kg/day H2
 - This units will also produce 240-960 kg/day of high purity O2
 - Production of O2 is cost effective in larger sizes







Summary

- Efforts are continuing on DOE Large Cell Grant
- Hugely difficult to get to 6,500 psig, with high purity, but we now think we have it done
 - We will also produce both H2 / O2 products
- The nested cell remains to be fully proven, but we believe the major risks have been reduced and will move forward with full scale testing and pilot plant
- Avalence will offer larger cells and higher capacity plants, at lower costs with new architecture
- We would like to acknowledge the patience and guidance of DOE





Contact Information

<u>CEO</u>: Anthony Della Volpe Operations and Funding ajd@avalence.com

<u>CTO:</u> Paul Dunn Technology Development pmd@avalence.com

Project Lead: Dave Mauterer dwm@gasequip.com





1240 Oronoque Road • Milford, Connecticut 06460 • Tel: 203-701-0052 • Fax: 203-878-4123 www.avalence.com -15-