

Extended durability testing of an external fuel processor for SOFC

Mark A. Perna, Anant K. Upadhyayula and Mark V. Scotto
Rolls-Royce Fuel Cell Systems (US) Inc.
May 15, 2012

Project ID: FC072

This presentation does not contain any proprietary, confidential, or otherwise restricted information

© **2012 Rolls-Royce Fuel Cell Systems (US) Inc.** This material is based upon work supported by the U.S. Department of Energy under Award Number DE-FG36-08GO88113 and pursuant to 10 CFR 600.325, Appendix A(c)(1), Rights in Data - Programs Covered Under Special Data Statutes (OCT 2003), Rolls-Royce Fuel Cell Systems (US) Inc. has granted to the Government, and others acting on its behalf, a paid-up nonexclusive, irrevocable, worldwide license to reproduce, prepare derivative works, distribute copies to the public, and perform publicly and display publicly, by or on behalf of the Government, for all such data.

Disclaimer: This presentation was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring the United States Government or any agency thereof. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government of any agency thereof.

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Overview

Timeline

- Project start: 08/01/2008
- Project end: 06/30/2012
- Percent complete: 90%

Budget

- Project funding total \$1,968,000
 - DOE share = \$984,000
 - RRFCS = \$984,000
- Funding received in FY11 = \$0
- Planned funding in FY12 = \$0

Barriers

Fuel Processor

- Durability
- Performance

Partners

- RRFCS – project lead
- Ohio Department of Development
 - Funding for Outdoor Test Facility
- Stark State College
 - Student Interns

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Relevance

Stationary power generation with fuel cells

Rolls-Royce Fuel Cell Systems (US) Inc. (RRFCS) believes its 1 MWe Solid-Oxide Fuel Cell (SOFC) power plant concept is best suited for stationary power generation applications. With its high electrical efficiency (~60%), negligible air emissions, and minimal noise profile, the concept is highly suitable for connection to local distribution networks in urban areas. The applications of interest include hospitals, universities, shopping malls, factory units, etc.

The 1 MWe SOFC power plant will be configured initially to use pipeline natural gas. Future development may target alternative fuels such as biogas.

RRFCS' SOFC power plant concept through its high efficiency, negligible air emissions and potential fuel flexibility directly supports the DOE Hydrogen and Fuel Cells Program's mission statement "to reduce petroleum use, greenhouse gas emissions, and air pollution and to contribute to a more diverse and efficient energy infrastructure by enabling the widespread commercialization of hydrogen and fuel cell technologies."

RRFCS' SOFC power plant concept for stationary power supports the DOE Hydrogen and Fuel Cells Program's goal to advance fuel cell technologies "...through research, development, and validation efforts – to be competitive with current technologies in cost and performance, and to reduce the institutional and market barriers to their commercialization."

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Technical barriers and targets

This project addresses technical barriers:

A – Durability and C –Performance from the Fuel Cells section of the Fuel Cell Technologies Program (FCT) Multi-Year Research, Development and Demonstration (RD&D) Plan. These barriers will be addressed as they relate to the external fuel processor in RRFCS’ 1 MWe SOFC power plant concept for distributed generation.

This project addresses the following technical targets:

| Technical Targets ^a : 100kW – 3 MW Distributed Generation Fuel Cell Systems Operating on Natural Gas ^b | | | | |
|---|----------------------------|-----------------------------|-----------------------------|---|
| Characteristic | DOE 2011 Status | DOE 2015 Targets | DOE 2020 Targets | RRFCS Targets mature product |
| Electrical efficiency at rated power ^c | 42-47% | 45% | >50% ^d | ~ 60% |
| System availability ^e | 95% | 98% | 99% | 95% |
| Sulfur content in product stream, ppbv ^f | <10 | | | <100 |

a - Includes fuel processor, stack and ancillaries. b - Pipeline natural gas. c - Ratio of regulated AC net output energy to lower heating value (LHV) of input fuel. d - Higher electrical efficiencies (e.g. 60% using SOFC) are preferred for distributed generation applications. e - Percentage of time available for operation. Unavailable time includes scheduled maintenance. f - Parts-per-billion, dry volume basis.

This presentation does not contain any proprietary, confidential, or otherwise restricted information

External fuel processor for SOFC

The external fuel processor for the RRFCS 1-MWe SOFC power plant concept uses only air and pipeline natural gas to provide all required gas streams for:

- **Start-up & shutdown – nonflammable reducing gas**
- **System heat-up and part-load operation – synthesis gas**
- **Normal operation - desulfurized natural gas**

The external fuel processor eliminates the need for on-site storage of high-pressure gas cylinders to supply hydrogen and nitrogen.

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Overall Objectives

- **Conduct long-term tests in relevant environments for the three fuel processor subsystems that support operation of the 1-MWe SOFC power plant. The subsystems include:**
 - Synthesis-gas subsystem
 - Start-gas subsystem
 - Desulfurizer subsystem
- **Determine long-term performance of key components such as catalysts, sorbents, heat exchangers, control valves, reactors, piping, and insulation**
- **Evaluate the impact of ambient temperatures (hot and cold environment) on performance and component reliability**
- **Determine system response for transient operation**

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Objectives

The project objectives from May 2011 through May 2012 included:

- **Complete Desulfurizer subsystems testing in outdoor test facility**
 - Operate Desulfurizer subsystem round-the-clock in an unattended mode for 8,000 hours by end of December 2011
- **Evaluate materials of construction for:**
 - Sorbent vessel used in the Desulfurizer subsystem
 - Reactor components in Synthesis-gas subsystem
- **Perform Start-gas subsystem testing to:**
 - Complete shakedown and commissioning
 - Confirm multiple system start-ups
 - Demonstrate operation of Start-gas subsystem

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Approach

Operate the three fuel processor subsystems on pipeline natural gas for extended periods. Conduct subsystem tests in relevant environments:

1. Synthesis-gas subsystem - up to 1,200 hours in warm environment
2. Start-gas subsystem - up to 200 hours in outdoor environment (hot / cold)
3. Desulfurizer subsystem - for 8,000 hours in outdoor environment (hot / cold)

Perform post- test inspections and analyses

- Physical and chemical analyses of catalysts, sorbents, piping, reactors, and insulation
- Functional checks of control valves, heaters, heat exchangers, control system sensors and safety system sensors
- Identify deposits and signs of wear, damage, corrosion or erosion

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Synthesis-gas subsystem test plan

- **Synthesis gas (H₂ and CO) is generated from pipeline natural gas and compressed air using a catalytic, partial oxidation reactor with automatic control system**
- **Operate Synthesis-gas subsystem for up to 1,200 hours**
 - Determine synthesis gas composition as a function of load (10%, 50% and 100% of design flow)
 - Determine impact of operating time on gas composition (hydrogen, carbon monoxide and methane)
 - Target performance - less than 10% reduction in H₂ over catalyst life
- **Perform 10 start-up cycles**
 - Determine impact of operating time on start-up and light-off
- **Perform post-test inspections**

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Start-gas subsystem test plan

- **Start gas is non-flammable or weakly flammable reducing gas generated from pipeline natural gas and an oxygen-depleted air stream**
- **Start-gas subsystem uses:**
 - Low-oxygen content oxidant stream generator
 - Catalytic reactor to generate hydrogen and carbon monoxide
 - Air-cooled heat exchanger to cool product gas
 - Automatic control system for unattended operation
- **Operate Start-gas subsystem for up to 200 hours**
 - Determine gas composition as a function of operating conditions
 - Determine impact of operating time on gas composition (hydrogen, carbon monoxide, and methane)
 - Target performance - less than 20% variability from target flammables content
- **Perform 24 start-up cycles**
 - Determine impact of operating time on start-up and light-off
- **Perform post-test inspections**

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Desulfurizer subsystem test plan

- SOFC requires high pressure (10 Bara) desulfurized natural gas with < 100 ppb total sulfur
- Desulfurizer subsystem uses:
 - Pipeline natural gas (1 to 10 ppmv sulfur) and compressed air as reactants
 - Catalytic reactor for oxy-desulfurization with high-capacity sulfur sorbent
 - Automatic control system for unattended operation
- Operate for up to 8,000 hours
 - Determine sulfur content in product gas as a function of load
 - Determine impact of operating time on product gas composition
 - Target performance
 - Less than 100 ppb sulfur in outlet gas - desulfurized natural gas
 - Total hydrocarbons (mostly methane) \geq 90% in desulfurized natural gas
 - Desulfurized natural gas retains > 98% of its original calorific value
 - Evaluate materials for sorbent vessel
- Perform post-test inspections

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Milestones - status

| No. | Description | Planned | Actual | Status |
|-----|--|------------|------------|--------------------|
| 1 | Start Preparation of Synthesis-gas Subsystem | Jan. 2009 | Jan. 2009 | completed |
| 2 | Begin Synthesis-gas Subsystem Durability Test | April 2009 | Sept. 2009 | completed |
| 3 | Start Preparation of Desulfurizer Subsystem | July 2009 | Dec. 2009 | completed |
| 4 | Complete Synthesis-gas Subsystem Durability Test | Sept. 2009 | April 2010 | completed |
| 5 | Complete 1,000 hours Operation of Desulfurizer | Sept. 2010 | Nov. 2010 | completed |
| 6 | Start Preparation of Start-gas Subsystem | July 2009 | Dec.2009 | completed |
| 7 | Begin Start-gas Subsystem Durability Testing | Sept. 2011 | Feb. 2012 | completed |
| 8 | Complete Desulfurizer Subsystem Test | Dec. 2011 | Dec. 2011 | completed |
| 9 | Complete Start-gas Subsystem Test | June 2012 | | on schedule |
| 10 | Complete Final Report | Sept. 2012 | | on schedule |

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Technical accomplishments and progress

● **Synthesis-gas subsystem testing completed April 2010**

- Results presented at DOE 2010 Annual Merit and Peer review Meeting
- Results received from post-test inspections and impact on life being assessed

● **Start-gas subsystem**

- Control software and mechanical hardware commissioned
- System shakedown completed
- Operation of subsystem confirmed March 30, 2012
- Multiple start-ups of subsystem confirmed March 30, 2012
- Plan prepared for durability testing


● **Desulfurizer subsystem installed in outdoor test facility**

- Control software and mechanical hardware commissioned
- Durability testing completed 8,000hrs of operation on November 15, 2011
- Sulfur removal targets achieved
- Results received from post-test inspections and impact on life being assessed

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Technical accomplishments and progress

Installation of Desulfurizer and Start-gas subsystems in outdoor test facility



This presentation does not contain any proprietary, confidential, or otherwise restricted information

Technical accomplishments and progress

Start-gas subsystem installed in outdoor test facility

- Control system commissioned
- Safety system commissioned
- Instrumentation calibrated
- Control valves tuned
- Gas sensors calibrated
- Start-up procedure confirmed
- Testing underway



This presentation does not contain any proprietary, confidential, or otherwise restricted information

Technical accomplishments and progress

Desulfurizer subsystem installed in outdoor test facility


- Control system commissioned
- Safety system commissioned
- Instrumentation calibrated
- Control valves tuned
- Gas sensors calibrated
- Durability testing started 10/2010
- Durability testing completed 11/15/2011 after logging 8,000hrs time-on-stream
- Sulfur target (<100 ppb) achieved



This presentation does not contain any proprietary, confidential, or otherwise restricted information

Technical accomplishments and progress


Desulfurizer subsystem durability testing results



- Durability testing started in September 2010
- Completed 8,000 hrs time-on-stream on 15th – November 2011

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Desulfurizer subsystem durability testing results ¹⁹



- Total sulfur in DNG mostly < 100 parts per billion (detection limit=10 ppb)
- Sulfur spikes observed in the outlet DNG at low load are being investigated
- Total hydrocarbons in DNG > 90% (volume basis)

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Synthesis gas subsystem post-test inspections

Evaluations of materials of construction

Synthesis-gas reactor parts after 1000hrs operation



Catalyst Holder



Reactor Outlet



Sleeve



Thermowell




Support Piece

- Samples submitted to metallurgy laboratory for analysis


This presentation does not contain any proprietary, confidential, or otherwise restricted information

Desulfurizer subsystem durability testing results

Evaluations of materials



**Metal Coupons
from
Desulfurizer**




Alternative materials (Nitronic[®]30 and S20910) showed significantly lower initial corrosion rates compared to SS316. These are being considered in the design for the fuel processor commercial product.

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Start-gas subsystem testing results



Required operating range



This presentation does not contain any proprietary, confidential, or otherwise restricted information

Start-gas subsystem durability testing results

- Typical SOFC start cycle with required flammables concentration from Start-gas subsystem
- Degradation Results after multiple start/stop cycles
 - Degradation indicated by progression of temp. profile downstream
 - Very little degradation observed



This presentation does not contain any proprietary, confidential, or otherwise restricted information

Collaborations

- **RRFCS is the project lead. Significant collaboration between RRFCS and the Ohio Department of Development (ODOD) was required to enable this project to go forward.**
- **The Ohio Department of Development provided funding (\$3 million) through Ohio's Third Frontier to expand the Fuel Cell Prototyping Center located on the campus of Stark State College. The expansion included:**
 - **Outdoor and indoor test facilities for use by RRFCS**
 - **Stark State College Fuel Cell Center (laboratory space for fuel cell education)**
- **Stark State College has associate degree programs in electrical engineering technology and mechanical engineering technology (with fuel cell option). RRFCS has eight current students or graduates of these programs as either interns or permanent employees to support this project and other fuel cell projects.**

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Proposed future work

2012

- Complete post-test analyses of Desulfurizer subsystem (Q2CY12)
- Complete durability testing of Start-gas subsystem (Q2CY12)
- Perform post-test inspections and analyses of Start-gas subsystem (Q2CY12)
- Issue final report for project (Q3CY12)

2013 – not part of this DOE project

- Operate the fuel processor subsystems with a large-scale SOFC

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Summary

An approach was developed and completed for testing durability and performance of an external fuel processor for a SOFC

- 8000-hr Desulfurizer subsystem durability testing was completed
- 1000-hr Synthesis-gas subsystem durability testing was completed
- 200-hr Start-gas subsystem testing is nearly completed
- Operational issues experienced during the project have been successfully addressed
- Material issues experienced during the project are being assessed and addressed

This presentation does not contain any proprietary, confidential, or otherwise restricted information

End of Presentation

Thank you!

This presentation does not contain any proprietary, confidential, or otherwise restricted information