H,**F**(Hydrogen and Fuel Cells Program

Maritime Fuel Cell Generator Project

Joseph W. Pratt Sandia National Laboratories June 19, 2014



Project ID # MT013

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Sandia National Laboratories is a multi-program laboratory managed and operated by Sandia Corporation, a wholly owned subsidiary of Lockheed Martin Corporation, for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-AC04-94AL85000.



Project Background





Project Concept

PEMFC unit replaces diesel generators, saving fuel cost and emissions.

Project Scope

Design, build, and deploy a containerized fuel cell system to supply portable power for refrigerated containers ("reefers").

- 100 kW (net) PEMFC and H₂ storage inside a 20-foot container.
- 6-month deployment on land and over the ocean.
- Strategic set of project partners, encompassing both the H₂-fuel cell and maritime communities.

Project Overview

Timeline:

- Start: Sept. 2013
- End: Dec. 2015
- 25% complete

Budget:

- Total: \$2.1M
 - DOE Share: \$712k
 - \$40k received in FY13
 - \$672k received & planned in FY14
 - DOT/MARAD* Share: \$700k
 - Received in FY13
 - Contractor Share (est.): \$700k
- Cost share pct. (est): 66%

MT Barriers Addressed:

- A: Inadequate standards
- E: Financing mechanisms (Lack of cost and performance data)

Hydrogen and Fuel Cells Program

• F: Inadequate user experience

Partners:

- Sandia (project manager)
- Young Brothers, Ltd.
- Foss Maritime
- Hydrogenics (*sub w/ cost share*)
- Hawaii Natural Energy Institute (HNEI)
- American Bureau of Shipping (ABS)
- US Coast Guard (USCG)
- Hydrogen Safety Panel

Relevance – Overall Project Objectives

- Lower the technology risk of future port fuel cell deployments by providing performance data of H₂-PEMFC technology in this environment.
- Lower the investment risk by providing a validated business case assessment for this and future potential projects.
- Enable easier permitting and acceptance of H₂-FC technology in maritime applications by assisting USCG and ABS develop hydrogen and fuel cell codes and standards.
- Act as a stepping stone for more widespread shipboard fuel cell APU deployments.
- Reduce port emissions with this and future deployments.



Relevance – FY14 Impact as related to Project Objectives

- FY14 Impact: Working alongside the code and safety officials from the beginning enables faster permitting and acceptance for this project and future maritime fuel cell deployments.
 - ✓ Objective: Familiarize maritime code and safety offices with the project and concept of hydrogen fuel cells in maritime applications
 - Objective: Produce preliminary prototype design and review with ABS, USCG, and the Hydrogen Safety Panel
- FY14 Impact: Enable technical and business case validation, lowering technology and business risk.
 - ✓ Objective: Produce data collection and analysis plan
- FY14 Impact: Maintain hydrogen infrastructure capability on Oahu in support of this and future strategic projects
 - Objective: Develop hydrogen supply plan in close coordination with existing resources

Approach: Project Phases and Selected Milestones





Accomplishment: Established partnership team and held project kick-off meeting / site tour



DOE: Project Sponsor and Local H₂ Infrastructure



Sandia: Technology Support and Project Management



DOT/MARAD: Project Sponsor



Young Bros. and Foss Maritime: Deployment Partners



Hydrogenics: Prototype Production and Support



HNEI: Local H₂ Facilitator



American Bureau of Shipping: Maritime *Product Certification*



Hydrogen Safety Panel: Project and prototype safety review



US Coast Guard and USCG Sector Honolulu: Maritime codes and standards



Accomplishment: Collaboratively determined prototype functional specifications

Performance

- At least 100 kW continuous at the plugs
- 240 VAC, 3-phase
- Hybrid battery/ultracap for inrush current
- 10-12 hrs/day on the dock and 28 hr on the barge
- 60-90 kg of H_2 stored at 5,000 psi
- Size and Weight
 - 20-foot Hi-cube ISO container; 81,000 lb max weight

Environmental

- Ambient temperature +2 C to +40 C
- Tolerate rain, wave wash, salt water intrusion during operation
- Tolerate side-to-side movement in 20-foot seas during operation
- Handled as ordinary container (not operating when moved)



LFCHydrogen and Fuel Cells Program

Accomplishment: Progress towards hydrogen supply arrangements

- Several options for H₂ supply on Oahu.
- Working to find the option that will:
 - Be available for the project (timing and capacity)
 - Fit with DOE goal to maintain and grow
 H₂ infrastructure to support FCEV
 deployments
- DOE is taking the lead on this task, working with DOD, HNEI, and others.



Graphic from DOE presentation, "Fuel Cell Road Vehicles in Hawaii" by Pete Devlin and Greg Moreland, 11/15/2013. Used with permission.

Accomplishment: Engaged maritime code and safety authorities and defined requirements

- Initial briefings to US Coast Guard HQ, US Coast Guard Sector Honolulu, and American Bureau of Shipping in October/November 2013.
 - USCG and ABS see the value of using the project to assist them in developing informed C&S for hydrogen and fuel cells.
 - DOT/MARAD, Young Bros, and Foss's partnership greatly facilitates this interaction.
- Periodic follow-up meetings to keep them informed.
- ABS meeting Feb. 19 at ABS in Houston.
 - Resolved jurisdiction question and agreed to work together on the project even though ABS certification is not required.
- Design review May 9.
 - 2-way information exchange and valuable prototype design feedback





Accomplishment: Ensuring safety is integrated into the project

- Began interaction with the Hydrogen Safety Panel (HSP) early: Nov. 2013.
- HSP has provided guidance on developing project safety plan.
- HSP involvement has "easing of the minds" effect: quicker acceptance of the technology and timely achievement of project milestones.
- Hydrogen safety and basic emergency response training will be provided to deployment personnel by PNNL's Hydrogen Emergency Response Training for First Responders unit.





Photo from DOE-EERE-FCTO publication "Safety, Codes, and Standards" available at http://www1.eere.energy.gov/hydi ndfuelcells/pdfs/fct_h2_safety.pdi



Accomplishment: Preliminary prototype design review with all project partners

• May 9, 2014 with all project partners (verbal update)





A Collaborative Project

Partner		Project Roles
U.S. DEPARTMENT OF ENERGY	DOE	Sponsorship, steering, H_2 supply coordination
AND THE OF THE OF THE OF	DOT/MARAD	Sponsorship, steering, and facilitation of maritime relationships
YOUNG BROTHERS Your Neighbor Island Partner	Young Bros. & Foss Maritime	Site preparations, prototype operation and routine maintenance
HYDROG (E) NICS	Hydrogenics (sub w/ cost share)	Design, engineer, build, commission, and support prototype unit
HNEI Hawai'i Natural Energy Institute University of Hawai'i at Mánoa	HNEI	Hydrogen supply logistics facilitation
ABS	ABS	Prototype design to maritime product standards
	US Coast Guard	Review and acceptance of prototype design and operation
Pacific Northwest	PNNL H ₂ Safety Program	Prototype and project safety review by HSP; Hydrogen Emergency Response Training for First Responders
Sandia National Laboratories	Sandia	Management and coordination, H ₂ materials & systems expertise, tech/business data collection and analysis

Remaining Barriers and Challenges

- **Challenge**: Maintaining a planned deployment start date of May 2015 because of the late contract placement with Hydrogenics.
- **Planned Resolution**: The prototype fabrication delay caused by late contract placement can be made up for by the extra time built into the commissioning and training phase.
- All other prototype-related milestones and deliverables will be delayed by approximately three months.
- No other milestones or deliverables are at risk.



Proposed Future Work: Following the Plan

• Remainder of FY14:

- Finalize prototype design with buy-in from code and safety officials.
- Finalize hydrogen supply arrangements.
- Finalize data collection and analysis plan.
- Begin prototype build.

• FY15 work to be accomplished:

- Finish prototype build, factory test, on-site commissioning, and training.
- Finish site preparations and conduct on-site H₂ safety training.
- Begin deployment testing and collect operational and cost data.
- Continue to use the leverage for education and outreach both in HI and in the worldwide maritime/port community.



Summary: Addressing Several MT Program Goals and Barriers

- Enabling faster permitting and acceptance for this and future maritime hydrogen and fuel cell deployments.
- Enabling technical and business case validation, lowering technology and business risk.
- Maintaining hydrogen infrastructure capability in the State of Hawaii in support of future FCEV rollout.
- Direct and indirect user experience with hydrogen and fuel cell technology in the far-reaching maritime and port sector.



The Maritime Fuel Cell Project:

A wholly-collaborative effort with early and continuous stakeholders feedback that will successfully break down non-technical barriers to hydrogen and fuel cell use.



Thank you!





Technical Backup Slides

HBEC

Project Schedule - Summary

	2013				2014											2015												
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28
	S	0	Ν	D	J	F	Μ	А	М	J	J	А	S	0	Ν	D	J	F	М	А	Μ	J	J	Α	S	0	Ν	D
 Phase 1: Establish project team and define prototype unit 1. Project team partnerships established 2. Prototype unit and project specifications finalized 																		Note: Prototype design and build activities are delayed										
 Phase 2: Design and Engineering of the Prototype Unit and the Site 1. Prototype unit engineering and design complete 2. Site engineering complete 																		months as explained on slide 14, but deployment date is not affected.										
 Phase 3: Procurement and Construction of the Prototype Unit and of Site Equipment 1. Prototype unit build and integration complete 2. Prototype unit operational test 3. Site preparations complete 																												
 Phase 4: On-site demonstration of Prototype Unit Prototype delivery to YB wharf Prototype unit operational test and turnover to HTB/YB Demonstration and analysis of prototype unit Final report(s) (DOE and MARAD versions) 																												