

Validation of an Advanced High Pressure PEM Electrolyzer and Composite Hydrogen Storage, with Data Reporting, for **SunHydro** Stations

Larry Moulthrop (PI), J Sieverman



7 June 2016

6:30 PM

**Project ID #
TV020**

Overview

Timeline

Project start date: Dec 2012
Project end date: June 2017
Percent complete: 95%

Budget / Funding

Total spent (3/31/16): \$ 2,679,258
Total project value: \$ 2,810,544
Cost Share Percentage: 50%

Targets/Barriers

- **\$2.00-\$4.00/gge (2007\$)**
- **Hydrogen Storage**
- **Codes and Standards**
- **Lack of current H₂ Refueling Infrastructure Performance and Availability Data**

Proton's Partners / Collaborators / Interactors

Air Products & Chemicals - *Composite Storage / control - Supplier*
SunHydro LLC - *Fueling Stations - Collaborator*
Toyota Motor Sales - *FCHV Vehicles - Interactor*

Relevance / Impact

Target / Barriers

Proton team Project Goals

\$2.00-\$4.00/gge

Advanced PEM MEAs: (SH#1)

Save Up to 8 kWh/kg H₂ - Ph. 2 Go/No-go

- 57 bar H₂, ambient O₂
- In full-scale 65 cell stack, electrolyzer

Compared to commercial 30 bar PEM

Adv. 57 bar PEM water electrolyzer (SH#1)

Save up to 3.6 kWh/kg H₂ - Ph. 2 Go/No-go

- Reduce H₂ gas drying purge loss
- Station mechanical compression to 70MPa

Compared to 30 bar H₂ supply

Hydrogen Storage

Adv. composite H₂ storage (SH#1 and #2)

Double useable storage per unit volume

- Cycle from 28 to 87MPa

Compared to first generation storage tubes

Relevance / Impact

Target / Barriers

Proton team Project Goals

Codes and Standards

Compact Component Arrangements:

Fit SH#2 station within 12m ISO container

- Safety and NFPA 2 code analysis
- Novel component arrangements
- Classified, non-classified zones
- Cooling, power, CSD, H₂ generation

Speed AHJ approval, reduce install cost

Lack of H₂ Refueling Infrastructure Performance and Availability Data

Collect and report SH station performance


Validate advanced technologies reliability

- SunHydro #1 station, SunHydro #2 station
- Energy use, # fills, kg dispensed, capacity
- Maintenance type and frequency, issues
- “%Uptime”, any safety or customer issues

Up to 24 months of station data

Approach

Safety Analysis for Novel Component Arrangement



- Hazardous Operations Analysis
 - Identify process hazards that could lead to safety related consequences
 - Recommend ways for reducing risk of events associated with identified hazards
 - Covers H2 generation, compression, storage, and dispensing, HVAC, and siting

Code Compliance Matrix



- Diagrams EX zone reduction using code-informed compact component arrangements
- Implements NFPA 2:2016 revisions
- Utilized for siting containerized fueling station in Washington, D.C.
- Enables means to streamline permitting and reduce installation costs

Approach

Novel Component Arrangement

Goal: 12m station package, reliable, maintainable, permitted

- 6m ISO Container (x2)
 - Non-EX container houses electrolyzer, power, and controls
 - EX-rated container houses compression, storage, chilling, and dispensing equipment
- Lightweight 2 hr. firewall allows adjacent placement of EX and non-EX containers



Approach

Individual site summary for
Sun Hydro #1 & #2

Station instrumentation
install (retrofit & new)

Monitor loads and status of
each H₂ subsystem

Report collected Station data
using H₂ Refueling Station
Templates to Hydrogen Secure
Data Center at NREL.

Quarterly reports: (>24 months)

H₂: kg produced, stored, dispensed, SAE J2719 quality, and costs

Energy: kWh/kg for production, compression, dispensing

Station reliability, maintenance, service data, and costs

Station Safety incidents, near misses and hydrogen leaks

Data Acquisition/Reporting



Accomplishments and Progress

task	Description	Apr 2016 Progress	Expected Completion Date	Percent Complete
1	57 bar High Eff PEM Stack	<i>Lessons learned from scale-up of process have been collected Stack has operated continuously as needed throughout year</i>	2014Q1	100%
2	57 bar 65 kg/d H ₂ Generator	<i>57 bar upgrade components proof tested and installed 57 bar system operated throughout year to support data collection 57 bar dryer system tuned and optimized for energy savings</i>	2014Q3	100%
3	Composite Storage	<i>Storage tube qualification completed Tubes delivered, installed, and commissioned Upgraded performance demonstrated</i>	2014Q2	100%
4	57 bar input Compressor	<i>Modifications for selectable input pressure completed Efficiency improvement with higher input pressure demonstrated</i>	2014Q3	100%
5	Safety, Code/ Zone Analysis	<i>State of MA permit issued, DC permit pending</i>	2016Q2	98%
6	Novel Comp. Arrangements	<i>SunHydro#2 design complete – 2X 20ft containers (generation & compression/storage) Container construction complete – installation in DC</i>	2016Q2	98%
7	Data Acquisition System	<i>Data acquisition hardware installed and operating for SH1 Data acquisition hardware installed for SH2 Data collection software changes for SH2 complete</i>	2015Q4	100%
8	Formal Data Reporting	<i>Data for Sun Hydro #1 reported to NREL for each quarter since 2013 Q4. Data for Sun Hydro #2 coincident with installation.</i>	2017Q2	65%

Accomplishments and Progress

Response to 2015 Reviewer's Comments

It is not entirely clear how broad the benefit of this project will be, beyond helping one company build two stations.

The project benefits include relative contribution of higher H2 generation pressure in reducing mechanical compression cost, field validation of Type II ground storage cylinders and a compact fueling station design optimized with the latest code compliances, and station data that highlights infrastructure development needs.

It would be good to see a discussion of how the project is supported by, and will support, automakers that are introducing fuel cell vehicles on the East Coast.

There are discussions happening regarding the future commercial use of the SH station in CT. Use of the SH station in DC is scheduled to begin in June 2016.

The project provides little or no detail about station costs.

The station costs include the energy to run the mechanical compressor, the electrolyzer, HVAC equipment, dispensing equipment, and lights and safety equipment, measured in \$/kWh. Costs vary by month based upon station use and uptime with an average of \$7.50/kg

Accomplishments and Progress


CSD Container Complete

- Compression, Storage & Dispensing (CSD) Container complete, including all internal plumbing and wiring
- Received at Proton
- Prepped to ship to DC



Generation Container Complete

- Hydrogen Generation Container complete, including plumbing, ventilation, and power, safety, and control panels
- Built at Proton
- Prepped to ship to DC



Accomplishments and Progress

SH1 Data Acquisition

- Adapted reports to incorporate integrated data collecting with APCI

SH1 Data Reporting

- Submitted reports since 2013Q4
- Improving procedures to ensure data reflects true fueling operation with the instrumented H₂ generator
- Showing 4-8 kWh/kg reduction (5-10%)

SH2 Data Acquisition

- Equipment tested and installed
- Data collection scheduled to begin in June 2016

Data Acquisition/Reporting

Item	Data	Units
Days last updated	2/20/2016	ml/day
Proton stack reserve capacity for data	2.5 hrs (5.0 kg)	kg/hr
General Station Information		
Energy Provider	Proton (2016) (2015 Proton (2014) (2013) (2012) (2011) (2010) (2009) (2008) (2007) (2006) (2005) (2004) (2003) (2002) (2001)	
Unique Station Identifier	2016010101	
Location	14400 S. 27th St., Suite 1000, Tukwila, WA 98162	City, State
GPS Lat	47.4527	degrees
GPS Lon	-122.2542	ml/day
General Booking Data	000000	ml/day
First Public Filling Date	2/20/2016	ml/day
Still in Operation (Y/N)	Y	
Facility at Site Operation	Y	ml/day
Process Plant Operation	Y	
(Production, Refueling, Both Production & Refueling)		
Co-Production (H ₂ & Electricity - No Refueling)	Y	
Co-Production (H ₂ & Electricity - With Refueling)	Y	
Production Method (Refueling, Electrolysis)	Refueling	
Production (if applicable)		
Refueling Infrastructure		
Refueling Method		
Production Infrastructure		
Electrolysis Type (PEM, Alkaline, etc.)	PEM	
Electrolysis Manufacturer	Proton (2016)	
Electrolysis Size	250	kg
Electric Power (if Electrolysis, kW, MW, Pk)	1000.000	kg 1250/h
Design Production Capacity	2.0	kg 1250/h
Installed Production Daily Operation	2.0	kg 1250/h
Design Electrical Production Capacity	200.000	kg
Output Pressure	35.0	bar
Compressors and Storage		
Compressor type(s) (axial/centrifugal and other)	2016010101	kg 1250/h
Compressor Capacity (kg 1250/h)	2.0	kg 1250/h
Peak Performance Discharging Capacity per hour	2.0	kg 1250/h
Method of Pressuring	Other	kg 1250/h
Pressure type and temperature	35.0 (20)	kg 1250/h
Storage		
Number of Storage Tanks	0	kg
Volume of tank(s) pressure and capacity	2.0 (20) (20)	kg
1. tank description	2016010101	kg 1250/h
2. number of tanks, pressure and capacity	2.0 (20) (20)	kg 1250/h
3. tank description	2016010101	kg 1250/h
4. number of tanks, pressure and capacity	2.0 (20) (20)	kg 1250/h
5. tank description	2016010101	kg 1250/h
Other Information		
Safety (if H ₂ Temp, N/A Temp)	20	degrees C
Hydrogen Refueling Fueling (if applicable)	Y	kg 1250/h
Discharge	Y	kg 1250/h
Pressure and H ₂ Storage Fueling (if applicable)	Y	kg 1250/h
Flammable H ₂ Storage Fueling (if applicable)	Y	kg 1250/h
Budget Filled	Y	kg 1250/h
Permit Filled	Y	kg 1250/h



Figure 1. SunHydro #1 Compression, Storage, Dispensing Containerized System



Figure 2. Hydrogen from Proton System Test Facility



Figure 3. Compression and Storage, SunHydro #1



CO2 Heat Exchanger R. 20-ton cylinder behind 2 hr Storage

Collaborations



Department of Energy, NREL and NPS - Installation and Operations

- *NPS Siting, A&E, Construction, O&M of SunHydro #2 through the NREL Station case study project*



SunHydro LLC Fueling Stations

- *Owner of SunHydro#1 station in Wallingford CT and SunHydro#2 station in Brentwood Washington DC*
- *Cost share provider*



Toyota Motor Sales - FCHV Vehicles

- *Provided FCHV-adv cars used at SH#1*
- *No cost lease with SunHydro LLC*



Air Products & Chemicals – Storage/control

- *Supplier of advanced storage, commissioning*
- *Supplier of programming and dispensing data services*

Future Work

Balance Phase 1 Major Activity

2Q'16 SunHydro#2 commissioning

-ACCOMPLISHED-

Phase 2 Major Activity

Ongoing Station data acquisition and reporting

Support NREL Hydrogen Station Case Study Project, provide lesson's learned and potential design improvements for site selection, A&E, construction, and M&O from Proton's perspective.

Project Summary

Relevance: Addresses DoE goal of <\$4/gge, MYPP barriers of H₂ storage, codes, and lack of station performance data

Approach: Adv. 57bar PEM water electrolyzer, next-generation 87MPa composite storage tanks, and skid-mounted compact refueling component arrangements with SunHydro#1 and SunHydro#2 stations. Data reporting 36+ months for both SunHydro stations with adv. components.

Tech Accomplishments: 57bar stack and system built and tested; SunHydro#1 and #2 advance storage installed; SH#1 data monitoring and energy measurements ongoing; 8 kWh/kg energy reduction; SunHydro#2 installation

Collaborations: SunHydro LLC (stations), Toyota Motors (vehicles), APCI (supplier storage upgrade and programming)


Future Work : SH#2 install, data reporting for SH#1 and SH#2

Larry Moulthrop 203-678-2188 LMoulthrop@Proton OnSite.com

Technical Back-Up Slides

Approach

Fueling Tech Validation Tasks




Proton® C Series PEM Electrolysis Stack

- **10 Nm³/hr stack for Navy Life Support Application in 2008**
 - 57 bar H₂ differential pressure
 - Over 1 million cell-hrs of validation
 - Currently in serial production
 - Over 18 months on-board submarines
- **Derivative 30 bar version in 2009**
 - Basis of C-Series 30 Nm³/hr commercial product design
 - Over 1.5 Million cell-hrs of customer field experience to date



PEM Electrolysis Life Testing – ‘Mature’



*Note: Non-operating time and restarts removed from graph



SunHydro #1 Operations

Jan 2011 – Dec 2015



>14,000 kg of hydrogen dispensed

>3,600 high pressure H2 fills

Serving fleet of 12 FCHV and paratransit



SunHydro #1 Diagram

- A. 75 kW photovoltaic array
- B. Net metering / grid connection
- C. 65 kg/d H₂ Generation from H₂O
- D. 30 hp / 87MPa H₂ Compression
- E. 135 kg H₂ Storage @ 83 MPa
- F. H35-Tamb / H70-T-20 Dispensers

