

# *High Temperature Electrolysis Test Stand*

**PI: James O'Brien**

**Presenter: Richard Boardman**

Idaho National Laboratory

June 14, 2018

Project ID # tv040

# Overview

## Timeline

Project Start Date: 4/1/2017

End Date: currently planned through FY20; Project continuation and direction determined annually by DOE

## Budget

FY17 DOE Funding: \$1.49M

FY18 DOE Funding: \$800k

## Barriers

This project addresses the following technical barriers from the Technology Validation section of the FCTO MYRDD Plan:

- (G) Hydrogen from Renewable Resources
- (H) Hydrogen and Electricity Co-Production


## Partners

- US DOE: Project Sponsor and Funding
- NREL: Power converter and front-end controller integration
- PNNL: HTE stack design
- SNL: front-end controller development and testing with respect to grid interactions

# Relevance

## Overall Objective:

- I. Advance the state of the art of High Temperature Electrolysis (HTE) technology by discovering, developing, improving and testing thermal/electrical/control interfaces for highly responsive operations
- II. Support the DOE-NE/EERE collaboration in Nuclear-Renewable Hybrid Energy Systems Integration
  - Develop infrastructure to support systems integration HTE operations up 250 kW scale
  - Support HTE research and system integration studies
  - Measure cell-stacks and performance and materials health under transient and reversible operation
  - Characterize dynamic system behavior to validate transient models used for process control
  - Demonstrate integrated operation with co-located dynamic thermal energy systems including a high-temperature, high-pressure water flow loop and a thermal energy distribution and storage system
  - Operate the HTE test station with co-located digital real-time simulators for dynamic performance evaluation and hardware-in-the-loop simulations



Three 5-kW<sub>DC</sub> HTE stacks used in INL 15 kW integrated pilot plant testing (ca. 2012)

## Impact to date vs Barriers

- Facility will be commissioned for initial HTE hydrogen production at the 5 kW scale this month




# Approach

- Deploy flexible 25 kW<sub>DC</sub> multi-stack and 250 kW<sub>DC</sub> HTE testing units in the INL Dynamic Energy Transport and Integration Laboratory (DETAIL)
  - Provide a testing platform to HTE technology developers to test stack performance under dynamic operating conditions
  - Demonstrate and characterize simultaneous coordinated multi-directional transient distribution of electricity and heat for multiple industrial process heat applications
  - Characterize system performance under flexible operating conditions
  - Simulate broader systems through the use of real-time digital simulators with hardware-in-the-loop
  - Document HTE operational and performance characteristics in a grid-dynamic environment
- Evaluate the potential of HTE systems to achieve efficient, low-cost hydrogen production with optimized operational profiles designed to take advantage of intermittent low-cost electricity and integrated process heat
  - Help industry identify HTE technology gaps relative to optimized stack and systems designs for hybrid systems applications
  - Document performance characteristics associated with intermittent HTE operations
  - Investigate the impacts of grid instability on HTE operations
  - Demonstrate the utility of HTE thermal integration with co-located systems

# NE-EERE Collaboration: Experimental Demonstration of Integrated Systems

## Dynamic Energy Transport and Integration Laboratory (DETAIL)

Objective: Demonstrate simultaneous, coordinated, controlled, and efficient multi-directional transient distribution of electricity and heat for power generation, storage, and industrial end uses.




# Approach: HTE Stack Integration and Control Scheme

- Stacks for cyclic operations
- Heat integration improvements
- Modular units
- Reversible operation
- Co-electrolysis
- Oxygen recovery


Test Article	Electrolysis Power at Design Condition (1.2 V, 0.5 A/cm <sup>2</sup> )
Button cell (2.5 cm <sup>2</sup> )	1.5 W
Single cell (16 cm <sup>2</sup> )	9.6 W
Small stack (100 cm <sup>2</sup> , 10 cells)	600 W
Large Stack (100 cm <sup>2</sup> , 50 cells)	3 kW
Multiple-stack modules (4 large stacks)	12 kW



Stack integration with heat supply & recovery



# Approach: HTE Stack Integration and Control Scheme



HTE system model with regulatory control schemes

## What's new?

- Versatile design for larger, User-Provided stacks
- Grid-level Front-End Controller (FEC)
- Responsive power converter tied to digital real-time simulation of grid and FEC
- Controllable steam supply
- Connected to Thermal Energy Distribution System
- Stack instrumentation and monitoring
- Connection to H<sub>2</sub> user (e.g. chemical synthesis with CO<sub>2</sub> feedstock)

# Approach

Milestone	Date	Status
Report on 25 kW HTE test systems design and stakeholder value	12/31/2017	complete
Demonstrate operability and data management of 25 kW HTE test station	3/31/18	Expected 6/15/18
Demonstrate HTE module response rate of 0-95% capacity in 30 minutes or less, with an electricity demand response rate of 0-98% capacity in 10 minutes or less.	9/30/2018	On schedule


Go/No-Go Decision	Date	Status
Successful initial operation of the flexible HTE 25 kW station	3/31/18	pending



# Accomplishments and Progress

- Completed Design and Installation of Facility Support Infrastructure

- ✓ Power,
- ✓ DI water system,
- ✓ drain, enclosure,
- ✓ ventilation system,
- ✓ H<sub>2</sub> vent,
- ✓ gas monitoring,
- ✓ safety interlocks,
- ✓ fire protection,
- ✓ structural support




# Accomplishments and Progress

- Completed Design and Installation of 25 kW HTE Test Facility
- Initial testing is currently under way
  - ✓ High-temperature furnace
  - ✓ High-temperature air supply for sweep gas
  - ✓ N<sub>2</sub> purge systems
  - ✓ Gas dryer and hydrogen recycle system
  - ✓ Gas monitoring system with interlocks Instrumentation
  - ✓ Methanol synthesis integration



# Accomplishments and Progress

## 25 kW HTE Research Facility



# Accomplishments and Progress



High Bay location of DETAIL within the INL Energy Systems Laboratory



DI Water System



4 kW HTE test stacks at INL, 2012



Steam Generator



Furnace



Hydrogen recycle compressor



Condenser array

# Accomplishments and Progress (Coordination)

## Established Technical and Functional Requirements for Dynamic Energy Transport and Integration Lab (DETAIL)


- Thermal and electrical integration to represent commercial-scale units
- Monitoring and controls performed locally, in communication with Power Systems/Grid Real-Time Digital Simulation (RTDS, right)
- Thermal energy relay to match nuclear reactor thermal hydraulics test loop
- Design of Phase I for Advanced Reactor Technology Integrated System Testing completed
- Thermal Energy Delivery System design underway



INL Power Systems/Grid Real-Time Digital Simulation (RTDS)



ARTIST Thermal Hydraulic Test Loop



## ***Reviewer Comments***

This project was not reviewed last year


# Collaboration and Coordination

## DOE Partnerships

- DOE-NE / DOE-EERE Collaboration
  - Nuclear-Renewable Hybrid Energy Systems

## Industrial Partnerships

- OxEon Energy
  - Stack development and testing
- Haldor Topsoe
  - Stack and system supplier
- Fuel Cell Energy
  - Large-scale systems
- Exelon
  - Grid stability, non-electric markets for nuclear
- Small Modular Nuclear Reactor
  - Joint-Use Modular Plant



OxEon Energy Ruggedized Hermetic CTE-Matched Solid Oxide Electrolysis Stack (graphic used with permission)

## ***Collaboration and Coordination***

### National Laboratory Partnerships

- PNNL
  - HTE Stack development
- NREL
  - Power converter and Front-End Controller testing
- SNL
  - Front-End Controller development and testing with respect to grid interactions



## ***Remaining Challenges and Barriers***

- Long-term performance of Solid Oxide Electrolysis Cell (SOEC) stacks
  - Degradation must be 0.5%/k-hr or lower for economic viability
  - Intermittent operation and thermal cycling may accelerate degradation
  - Reversible operation may improve long-term degradation characteristics
  - Effects of grid instability on HTE system performance must be determined
- Optimization of HTE operation in dynamic environment for achievement of low-cost H<sub>2</sub> production while providing grid stabilization services
- Reduction of HTE system capital costs
- Effective thermal integration and thermal management for intermittent/reversible operation

# *Proposed Future Work*

## Remainder FY18

- Complete Initial HTE testing in new facility at the 5 kW scale
  - Steady-state, baseline testing; long-term degradation
  - Effects of intermittent operation and thermal cycling
- Complete initial HTE test campaign at 25 kW scale (FY18/19)
  - Exercise full system capacity
  - Steady-state, baseline testing; long-term degradation
  - Effects of intermittent operation and thermal cycling
  - Operation with variable front-end power profiles
- Support the advancement of HTE stack technology, working with industry partners, for robust performance even with the demanding load profiles associated with deployment in flexible hybrid energy systems

## FY19

- Thermal integration of 25 kW system with the DETAIL thermal network
- Conduct 25 kW grid demand response exercises, documenting the thermal energy latency and system electrical characteristics

Note: Any proposed future work is subject to change based on funding levels

# ***Technology Transfer Activities***

- Working with HTE Systems Integration Companies
  - FuelCell Energy
  - OxEon
  - Boeing Company
  - Others...
- CRADAs with Industry
  - Exelon/Fuel Cell Energy (Poster No. h2052)
  - TerraPower
  - Terrestrial Energy, USA
- Working with large companies to identify new markets for large-scale hydrogen production with thermal integration
  - Direct-reduced iron
  - Grid stabilization
  - Enhanced profitability for existing light-water reactor fleet (non-electric application)
  - Synthetic liquid fuels

# Summary

*Objective:* Advance the state of the art of High Temperature Electrolysis (HTE) technology while demonstrating grid and thermal energy integration

*Relevance:* The growing contribution of renewable sources of electric power onto the grid requires increased flexibility in dispatchable energy producers. Appropriately staged hydrogen production via HTE provides a potential high-value product for increased profitability

*Approach:* Establish a large-scale High-Temperature Electrolysis test capability within the INL Dynamic Energy Transport and Integration Laboratory for demonstration and characterization of simultaneous coordinated multi-directional transient distribution of electricity and heat for multiple industrial process heat applications

*Accomplishments:* Design and installation of a flexible 25 kW HTE test facility has been completed and initial testing is in progress

*Collaborations:* Collaborations have been established with several National Laboratory and industry partners.

# ***Technical Backup Slides***

# Nominal operating conditions for full 25 kW testing

## Assumptions

- Acell = 12 cm x 12 cm
- Ncells = 50
- Nstacks = 4
- ASR = 0.6 Ω cm<sup>2</sup>
- i = 0.67 A/cm<sup>2</sup>
- steam utilization, U = 0.6
- inlet mole fraction steam: 0.7, 0.9
- inlet mole fraction H<sub>2</sub>: 0.1
- inlet mole fraction N<sub>2</sub>: 0.2, 0.0
- Air sweep gas, Nstoichs = 0.5

Flow Rates	With N <sub>2</sub>	No N <sub>2</sub>	units
H <sub>2</sub> in	32.0	24.9	SLPM
H <sub>2</sub> Production rate	134.5	134.5	SLPM
H <sub>2</sub> out	166.5	159	SLPM
H <sub>2</sub> O in (liq)	180	180	gm/min
H <sub>2</sub> O in (liq)	10.8	10.8	kg/hr
H <sub>2</sub> O in (steam)	224	224	SLPM
H <sub>2</sub> O out (steam)	89.6	89.6	SLPM
N <sub>2</sub> in	64	0	SLPM
Total Cathode gas flow in	320.2	249	SLPM
Air in	160	160	SLPM
O <sub>2</sub> Production rate	67.2	67.2	SLPM
Air+O <sub>2</sub> out	227	227	SLPM
	8.03	8.03	SCFM
<b>Recycle Flow Rates</b>			
Recycle compressor flow rating (@150 psig discharge pressure)	6.1	6.1	SCFM
Recycle compressor VFD setting	100	75	% of FS
H <sub>2</sub> through beds (avg)	1.131	0.879	SCFM
H <sub>2</sub> O into beds (avg)	0.0038	0.0021	SCFM
N <sub>2</sub> Through beds (avg)	0.435	0	SCFM
H <sub>2</sub> through beds (during compressor operation)	4.285	4.221	SCFM
H <sub>2</sub> O through beds (during compressor operation)	0.014	0.0103	SCFM
N <sub>2</sub> Through beds (during compressor operation)	1.648	0	SCFM
N <sub>2</sub> added after recycle	1.826	0	SCFM
<b>Stack Electric</b>			
Cell voltage	1.309	1.302	V
Stack voltage	65.5	65.1	V
Stack current	96.5	96.5	A
Module current	385.9	385.9	A
Module Power	25.3	25.1	kW
<b>Hot Zone</b>			
Operating Temp	800	800	°C
<b>Heater Power Requirements</b>			
Steam generator (H <sub>2</sub> O from 20 to 150 C)	8.1	8.1	kW
Superheater (H <sub>2</sub> +N <sub>2</sub> from 20 to 800 C + steam from 150 C to 800 C)	5.87	4.15	kW
Air heater/ superheater	2.87	2.85	kW