



# Maritime Fuel Cell Generator Project

Lennie Klebanoff Sandia National Laboratories May 31, 2020



Photo property of Sandia National Laboratories, courtesy of Bruce Appelgate, Scripps Institution of Oceanography

# Project ID #ta009

#### This presentation does not contain any proprietary, confidential, or otherwise restricted information

Sandia National Laboratories is a multi-mission laboratory managed by National Technology and Engineering Solutions of Sandia, LLC, a wholly owned subsidiary of Honeywell International Inc., for the DOE's National Nuclear Security Administration under contract DE-NA0003525



### We have built and deployed a containerized hydrogen fuel cell generator for reefer power on land and sea. <u>Project Concept</u>







Fuel cell unit replaces diesel generators, reducing fuel cost and emissions.

#### Project Scope (2013-present)

Design, build, and deploy a containerized fuel cell system to supply portable power for refrigerated containers ("reefers").

- 100 kW (net) fuel cell and H<sub>2</sub> storage inside a 20-foot container, ~ 4kW B.O.P.
- Strategic set of project partners, encompassing both the H<sub>2</sub>-fuel cell and maritime communities.
- Initial deployment with Young Bros. HI.
- Upgraded the MarFC to 480VAC operation for general marine service.
- Deploy with the Scripps Institution of Oceanography for shore power.



### **Project Overview**

#### **Timeline:**

- Start: July 2016
- End: January 2021
- 85% complete

#### **Budget:**

- Total: \$1.342 M
  - DOE FY16: \$258K
  - DOE FY17: \$279K
  - DOE FY19: \$150K
  - DOE FY20: \$50K
  - DOT/MARAD\* FY17: \$211K
  - DOT/MARAD\* FY18: \$329K
  - DOT/MARAD\* FY19: \$0K
  - DOT/MARAD\* FY20: \$65K

#### MT Barriers Addressed:

- A: Inadequate standards
- E: Financing mechanisms (Lack of cost and performance data)
- F: Inadequate user experience

#### Partners:

- Sandia (project manager)
- Scripps Institution of Oceanography (SIO)
- Hydrogenics (sub w/ cost share)





#### **Relevance – Overall Project Objectives**

- Lower the technology risk of future port fuel cell deployments by providing performance data of H<sub>2</sub>-PEMFC technology in this environment. (*Barrier: E*)
- ✓ Lower the investment risk by providing a validated economic assessment for this and future potential projects. (*Barrier: E*)



- Enable easier permitting and acceptance of  $H_2$ -FC technology in maritime applications by assisting USCG and ABS develop  $H_2$ +FC codes and standards. (*Barrier: A*)
- Engage potential adopters/end users of hydrogen fuel cells to enable more widespread acceptance of the technology. (*Barrier: F*)





#### **Approach: July 2019 - Present**

- Complete upgrade of the MarFC generator for 480 VAC operation.
- Perform 2-week test of upgrades for long-term stability and on/off cycling.
- Ship the unit from Mississauga Canada to SIO in San Diego CA.
- > Inspect unit after arrival for possible damage in shipping (repair as needed).
- > Engage  $H_2$  Gas Suppliers to secure fueling contract for the MarFC.
- Introduce/train SIO staff to the MarFC hydrogen fuel-cell technology.
- > Provide power to the *R/V Robert Gordon Sproul*, assess operation.
- > Deploy with SIO for 6 months, providing zero-emission shore power.
- Write Final Project Report





### Accomplishments and Progress: Completed MarFC Upgrade to 480VAC Operation



0	3-PHASE T	RANS	FORMER	2	0
TYPE: 3LT1601 FREQUENCY:	125-Dynyn11-23/PT/ 60 Hz IP:	/S AL : 23	ART.NO.: ORDER: BUILT (W-	3-030- 27548 Y): 0	001251 28- 1 17-2019
IN	PUT/PRI		OUTPUT/S	EC	
CONN. L1-L2-L3 Link: 10-146, 10-108, 19 10-168, 10-108, 19 10-168, 10-10, 19 10-168, 10-10, 19	VOLT AMP. COUP 1-56 +2:22.5% 1-36 +2:5% 1-36 +2:5% 1-36 -2:5% 1-36 -2:5%	2U-2V-2 3U-3V-2	VOLT 2W 480 3W 230	AMP. 144 100	COUPL ynti ynti
KVA: 160 Pk Juty: Cont. Po Cooling:AN A	W0:2217 ez%:5,07/1,27 W0:696 sr%:1,12/0,26 ux(W0:NA	7 Al Weig 5 Fe Weig Tot. Weig	ht: 105 Kg. Ins ht: 338 Kg. Am ht: 560 Kg. Ao	ul. Class: ibient tex o.to: IEC-	F np.: 45°C 60076-11

Nameplate of new transformer.



New recessed connector panel/box mounted on the MarFC unit to SIO specifications.

New 480VAC transformer installed



## Accomplishments and Progress: Tested Upgrades to MarFC Unit Over 2 Weeks



MarFC testing after upgrade



Unit tested for:

- ✓ 480 VAC 3-phase operation,
- ✓ Voltage stability, check for spikes,
- ✓ Starting and stopping.
- ✓ Endurance for 10 hours,
- ✓ Variable loads.

After testing, the unit was loaded onto a truck for shipment to San Diego.



**H\_FC**Hydrogen and Fuel Cells Program

### Accomplishments and Progress: MarFC Arrives at SIO with Damage, Repair Unit On-site

The unit arrived at SIO on 11/11/19 with broken PVC piping on the fuel-cell coolant recirculation system. On 12/1/19 the old glycol coolant fluid was drained, the broken piping was removed, new piping installed and new glycol fluid added.



Dave Haywood (Hydrogenics/Cummins) drains old coolant from the MarFC system.



Max Muller (Hydrogenics/Cummins) removes broken PVC piping



New Gray PVC coolant pipe successfully installed



H2FCHydrogen and Fuel Cells Program

## Accomplishments and Progress: Completed First Mobile H<sub>2</sub> Refueling of the MarFC

#### First on-site MarFC refueling via $H_2$ delivery on 12/2/19 by IGX.



IGX  $H_2$  refueling truck arrives at SIO



Cascade fill from IGX 350 bar truck tanks

![](_page_8_Picture_8.jpeg)

Successful H<sub>2</sub> connection, grounding truck to unit.

![](_page_8_Picture_10.jpeg)

Monitoring MarFC tank temperature during fill.

Refueling the MarFC via cascade fill from IGX  $H_2$  delivery truck was straightforward

![](_page_9_Picture_0.jpeg)

## Accomplishments and Progress: Completed SIO Education/Training 12/3/2019

SIO staff learn about the layout, use and refueling of the MarFC both in the classroom and on the Pier.

![](_page_9_Picture_4.jpeg)

Scripps personnel

![](_page_9_Picture_6.jpeg)

Craig Van Pelt (IGX) describes the H<sub>2</sub> refueling procedures

Sandia National Laboratories	H_FC Systemates and Faul Cutte Program
On the Physical and Co	ombustion Properties of
Hydrogen Compa	ared to Natural Gas
Lennie I	Klebanoff
Sandia Nation	al Laboratories
Livermore	e, CA 94551
Scripps Institution	n of Oceanography
San Di	ego, CA
Decemb	er 3, 2019
bando famino i alconomia i a contenuario bienere con que actorem en la ferencia e famigad	fantani fashani ya wa fingananya kitalami af kanto kili, a akata navari ashaniani af manana kanani dinada, akatanangkar anar samari ki kitalakili.
Sandia National Laboratories	REFORMANCE and Tool Calls Program

Lennie Klebanoff describes the properties of H<sub>2</sub> to SIO staff

![](_page_9_Picture_10.jpeg)

Max Muller gives a tour of the MarFC H<sub>2</sub> storage

![](_page_9_Picture_12.jpeg)

Max Muller describes the MarFC layout

![](_page_9_Picture_14.jpeg)

...and then of the fuel cell rack and power electronics

![](_page_10_Picture_0.jpeg)

**H\_FC**Hydrogen and Fuel Cells Program

## Accomplishments and Progress: First Fuel-Cell Powering of a Vessel: 12/19/2019

The first vessel powering by fuel-cell shore power-the *R/V Robert Gordon Sproul. Mechanical Systems.* 

![](_page_10_Picture_4.jpeg)

Connecting vessel cable to MarFC.

![](_page_10_Picture_6.jpeg)

Powering deck crane.

![](_page_10_Picture_8.jpeg)

Powering fire pump systems

![](_page_10_Picture_10.jpeg)

Powering Deck Pump.

Sequentially brought Sproul power systems online with the MarFC. The cumulative power after each step was:

- -- Lights, AC ,1 ventilation fan: ~ 22 kW
- -- Hydraulics, 2nd ventilation fan: ~ 36 kW
- -- Fire, steering pumps: ~ 50 kW
- -- Crane operation: ~ 65 kW

Largest transient spike in total power seen was ~ 83 kW.

All mechanical system power loads handled by the MarFC.

![](_page_11_Picture_0.jpeg)

![](_page_11_Picture_1.jpeg)

### Accomplishments and Progress: First Fuel-Cell Powering of a Vessel: 12/19/2019

#### Checking the more sensitive Computer and Science Systems.

Capt. Chris Welton checking the Sproul uninterruptable power supply (UPS) systems in the science bay.

![](_page_11_Picture_5.jpeg)

...and the Sproul computer systems and backup UPS systems under MarFC power.

Attempted MarFC powering of the Sproul Computer and Science Systems was not successful as the vessel UPS systems turned on and drained their batteries. Other UPS systems cycled on and off. These issues were traced to a MarFCvessel interface grounding issue, with no damage to the vessel power systems.

The fix to the problem has been designed, and will be tested when operations begin again after the California Shelter in Place order has lifted.

![](_page_12_Picture_0.jpeg)

![](_page_12_Picture_1.jpeg)

#### Summary

- Upgraded the MarFC unit to 480 VAC operation.
- Tested the upgrades over 2 weeks for proper operation.
- Shipped the MarFC to the SIO in San Diego, CA.
- > Secured  $H_2$  fueling contract with IGX.
- Inspected the MarFC, repaired damage sustained in transit.
- > Provided education/training to SIO staff on the  $H_2$ /MarFC technology.
- > Conducted first  $H_2$  fueling of the MarFC by  $H_2$  delivery truck.
- > Conducted first powering of the *R/V Robert Gordon Sproul*.

![](_page_13_Picture_1.jpeg)

### **Proposed Future Work**

- Implement the unit repair that resolves the MarFC-vessel interface grounding issue.
- Demonstrate via pierside test that the MarFC functions as expected.
- Attempt another powering of the *R/V Robert Gordon Sproul*, monitoring mechanical, computer and science systems.
- Conduct 6-month demonstration using the MarFC to provide shore power to the Sproul.
- Collect and analyze data from 6month deployment.
- Write Final Report.

![](_page_13_Picture_9.jpeg)

Photo Credit: Bruce Appelgate, SIO

Any proposed future work is subject to change based on funding levels

![](_page_14_Picture_0.jpeg)

![](_page_14_Picture_1.jpeg)

# **Collaboration and Coordination**

Thanks to our partners and colleagues:

- Scripps Institution of Oceanography: Bruce Appelgate, Zoltan Kelety
- Hydrogenics/Cummins: Ryan Sookhoo, Nader Zaag, Luis Orosco, Max Muller, Dave Haywood.
- IGX: Craig Van Pelt, DeLisa Leighton, Michael Koonce.
- Sandia National Laboratories: Madelynne Farber, Jon Zimmerman

![](_page_15_Picture_0.jpeg)

![](_page_15_Picture_1.jpeg)

### **Thank You!**

![](_page_15_Picture_3.jpeg)

![](_page_16_Picture_0.jpeg)

![](_page_16_Picture_1.jpeg)

# **Publications and Presentations**

- No publications were produced from the work.
- "Development of a Containerized 100 kW Fuel Cell System for Maritime Applications," Lennie Klebanoff presentation to H2@Ports DOE Workshop, San Francisco, CA September 11, 2019.
- "Maritime Fuel Cell Generator Project," DOE H<sub>2</sub> Program Annual Merit Review, Washington D.C., May 31, 2020.

![](_page_17_Picture_0.jpeg)

![](_page_17_Picture_1.jpeg)

# **Critical Assumptions and Issues**

1. We need to find a deployment site that does not require indemnification.

SIO satisfies this requirement.

 Cost of delivered hydrogen is still currently high (> \$50/kg), which is a burden on the deployment site.

We are working with the H<sub>2</sub> suppliers to provide hydrogen within the existing project funding.