

Controlled Hydrogen Fleet and Infrastructure Demonstration and Validation Project

TEAM:

Chevron Technology Ventures

Hyundai-Kia Motor Company

UTC Power

Puneet Verma – Program Manager

Dan Casey – Technical Director

Chevron Hydrogen

May 2007



Timeline

- January 15, 2004
- September 30, 2009
- 45 % complete

Budget

- Total project funding - \$93.9 mil
 - DOE share - \$37.8 mil
 - Contractor share - \$56.1 mil
- Prior Funding - \$16.1 mil
- Funding FY07 - \$ 0.5 mil

Barriers

- Vehicles
- H2 Refueling Infrastructure
- Codes & Standards

Team Members

- Hyundai-Kia Motor Companies
- UTC Power
- Hyundai Kia America Technical Center
- Alameda Contra Costa Transit
- Southern California Edison
- Tank Automotive Research, Development and Engineering Center (DOD)
- Gas Technology Institute

<p>Overall</p> <p>FC Stack Durability: >2000 hr</p> <p>Vehicle Range: >250 miles</p> <p>Hydrogen Cost: <\$3.00/gge</p>	<p>Obtain data to validate 2009 performance targets</p> <ul style="list-style-type: none"> •Collect: <ul style="list-style-type: none"> – FC vehicle operating data •Demonstrate: <ul style="list-style-type: none"> – Different methods of on-site hydrogen generation
<p>2006</p>	<ul style="list-style-type: none"> •Hydrogen safe chassis dyno and Maintenance facility •Test different climatic conditions on FC vehicles •Three On-site Generators <ul style="list-style-type: none"> – Rosemead – Oakland – Orlando (not funded by DOE)
<p>2007</p>	<ul style="list-style-type: none"> •Increase Vehicle availability and reliability •Improve Vehicle Performance with 2nd Gen. vehicles •Operate and report from 5 on-site generation stations •Construct and Operate Partial Oxidation Gas Turbine (POGT)

 Milestone 2	Demonstrate 50% higher fuel economy <ul style="list-style-type: none">➤ Conduct Dyno testing – initial testing complete➤ Conduct on road testing – data reported to NREL monthly
 Milestone 3	Demonstrate 2005 energy and mass density targets <ul style="list-style-type: none">➤ 350 bar vehicles on the road➤ 700 bar vehicle to be tested
 Milestone 5	Validate vehicle range of ~200 miles and 1000 hours <ul style="list-style-type: none">➤ On road testing data being reported to NREL monthly
 Milestone 6	Validate refueling less than 5 minutes <ul style="list-style-type: none">➤ Work complete
 Milestone 11	Validate \$3/gge production cost <ul style="list-style-type: none">➤ On-site hydrogen generation stations in operation
 Milestone 12	Five station and two maintenance facilities constructed. <ul style="list-style-type: none">➤ Data reported to NREL from 2 stations➤ Three additional stations on line 1Q 2007➤ Maintenance facility operational in Chino


Approach – Infrastructure



Approach – Vehicle Deployment



Operation Area	Service Facility	Site Host Location	Operator	Total	2005	2006	2007
Southern California	Chino	Chino	HATCI	6	3	2	1
		Rosemead	SC Edison	9	0	0	9
Northern California	Sacramento	Sacramento	CARB	1	0	0	1
		Oakland	AC Transit	11	1	6	4
Michigan	Ann Arbor	Selfridge	TARDEC	5	0	0	5
3 Regional Areas			5 Organizations	32	4	8	20



<h2>Design</h2>	<h2>Construction</h2>
<ul style="list-style-type: none">• Process Flow Diagram, Equipment Layout, and Piping & Instrumentation Drawings Completed	<ul style="list-style-type: none">➤ Partial Oxidation Gas Turbine (POGT) and Partial Oxidation Reactor (POR) Integration in Progress
<ul style="list-style-type: none">• HazOp Review Completed	<ul style="list-style-type: none">➤ Water Gas Shift (WGS) Slipstream Unit Fabricated
<ul style="list-style-type: none">• PSA System and Gas Analysis Available	<ul style="list-style-type: none">➤ Compressor and Buffer Tank Received

Alameda County Transit (ACT)

- 30 more employees have been trained in vehicle operation since last review for a total of 50
- ACT performed maintenance and light repair of 3 of their fleet vehicles
- HATCI has provided an updated Routine Maintenance Check sheet along with photos

Southern California Edison (SCE)

- 5 employees have been trained in vehicle operation at Southern California Edison
- 3 employees have been trained in vehicle maintenance at Southern California Edison

Safety and ER Training

- HATCI has participated in First Responder Training in both Northern and Southern California
- Zero Vehicle Accidents





- 20 kg/day generation capacity
- 60 kg storage
- Single dispenser
- 5000 psig
- Fill rate – up to 3.6 kg/min



- 40 kg/day generation
- 312 kg storage
- Single Dispenser
- 5000 psig
- Fill rate – up to 3.6 kg/min



- 114 kg/day generation
- 312 kg storage
- Single Dispenser
- 5000 psig

Slipstream Water-Gas-Shift Reactor
(shown uninsulated)



Partial Oxidation Gas Turbine System


Partial Oxidation Reactor (POR)

Partial Oxidation Gas Turbine (POGT)



➤ Hot test performed at Death Valley on Jul. 2006

- Test region : Death Valley & Mojave PG(HMC)
- Test modified cooling module




July '06 @ Death Valley

- Achieved improved cooling performance
 - No power degradation
 - Positive water balance at Daylight and Towne pass


Sub-zero start up performance

➤ Cold start up test successfully performed on Feb. 2007

- Test region : UTC Power (Hartford, CT)
- Cold climate soaking time : more than 3 days



Tested at UTC Power with HMC engineers




Vehicle Service Facilities

➤ Hydrogen Safe Dyno Bay (Chino)




- H2 Safety Dyno Cell :
Chino, CA ('07. 3)
- H2 Safety Work Bay :
 - CaFCP (5 vehicle bay)
 - Chino, CA (1 vehicle bay)
 - Selfridge, MI (Under Construction)
 - Seminary, CA(1 veh. Tent)
 - Pomona, CA (1 veh. Bay)

➤ Hydrogen Safe Work Bay (Chino)



Fleet Monitoring and Data Collection




- 5 Local servers added
- 8 Local servers installed
- AC Transit (4)
- SC Edison (1)
- TARDEC (1)
- HATCI : Chino (1), CaFCP (1)

Data to NREL


Lesson Learned Storage Inventory Calculation

Use First Order Filter on Temperature Measurement

Peak Pressure Lags Peak Ambient Temperature



"Constant" Mass calculation varies with time of day



- Ambient temperature external of storage is used for mass calculation
 - Eliminates electrical equipment in C1D2GB electrical area
 - Eliminates penetration into high pressure storage vessel
- However, Peak pressure does not coincide with peak daily temperature
 - Delay is due to heat transfer from ambient to massive steel vessels
- Mismatch leads to error and variation in "constant" mass calculation
- First order filter reduces standard deviation of calculated mass by a factor of 10

- Field 32 Vehicles
 - by the end of 2007
- Collect operating data from Stations in:
 - Rosemead, CA
 - Selfridge, MI
 - Orlando, FL*
- POGT Testing 2nd quarter



*not in DOE program but data to be shared with DOE

Relevance

- FC vehicle real world operating data
- On-site hydrogen generation demonstration

Approach

- Fleet testing of 32 FC vehicles
- Operation of six on-site hydrogen generators
 - Reformers CSA 5.99 US Certified

Technical Accomplishments and Progress

- Range and Durability reported to NREL
- Two stations reported to NREL
- Third Party fuelings conducted at stations

Technology Transfer

- Lessons learned included in merit review

Proposed Future Work

- Continue testing of vehicles and data reporting to NREL

Fleet Monitoring and Data Collection

Strategy

- 1) Provide safe and delightful driving to partners
- 2) Provide quick maintenance
- 3) Monitor the route and encourage usage

